

EARTH EXCAVATION					
Location		Earth Excavation	Excavation to be used in Embankment	Embankment	Earthwork Balance**
From	To	Cubic Yard	Cubic Yard	Cubic Yard	Cubic Yard
439+25	444+00	365	274	583	-309
Total		365	274	583	-309

* Adjusted for Shrinkage (25% Shrinkage Assumed)
 ** Waste (+) or Shortage (-)

SEEDING, CLASS 2			
Nokomis Road			ACRE
439+25	to	444+00	0.50
Total			0.5

STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS				
Nokomis Road				FOOT
440+18.50	to	440+81.00	Rt	62.5
440+80.00	to	440+92.50	Lt	12.5
442+35.50	to	442+48.00	Rt	12.5
442+47.00	to	443+09.50	Lt	62.5
Total				150.0

BITUMINOUS MATERIALS (PRIME COAT)			
Nokomis Road			GALLON
439+25.00	to	441+28.17	270.89
441+99.83	to	444+00.00	266.92
Total			538

MULCH, METHOD 2			
Nokomis Road			ACRE
439+25	to	444+00	0.50
Total			0.5

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT				
Nokomis Road				EACH
439+68.50	to	440+18.50	Rt	1
443+09.50	to	443+59.50	Lt	1
Total				2

BITUMINOUS MATERIALS (COVER AND SEAL COATS)			
Nokomis Road			GALLON
439+25.00	to	441+28.17	541.79
441+99.83	to	444+00.00	533.84
Total			1076

NITROGEN FERTILIZER NUTRIENT			
0			POUND
439+25	0	444+00	45.00
Total			45

TRAFFIC BARRIER TERMINAL, TYPE 2				
Nokomis Road				EACH
440+67.50	to	440+80.00	Lt	1
442+48.00	to	442+60.50	Rt	1
Total				2

PHOSPHORUS FERTILIZER NUTRIENT			
Nokomis Road			POUND
439+25	to	444+00	45.00
TOTAL			45

TRAFFIC BARRIER TERMINAL, TYPE 6A				
Nokomis Road				EACH
440+81.00	to	441+24.00	Rt	1
440+92.50	to	441+35.50	Lt	1
441+92.50	to	442+35.50	Rt	1
442+04.00	to	442+47.00	Lt	1
Total				4

POTASSIUM FERTILIZER NUTRIENT			
Nokomis Road			POUND
439+25	to	444+00	45.00
TOTAL			45

COVER COAT AGGREGATE			
Nokomis Road			TON
439+25.00	to	441+28.17	6.77
441+99.83	to	444+00.00	6.67
Total			13.4

AGGREGATE BASE COURSE, TYPE A 8"			
Nokomis Road			SQ YD
439+25.00	to	441+28.17	519.2
441+99.83	to	444+00.00	511.5
Total			1031

SEAL COAT AGGREGATE			
Nokomis Road			TON
439+25.00	to	441+28.17	6.77
441+99.83	to	444+00.00	6.67
Total			13.4

FILE NAME =	USER NAME = HURST-ROSCHE	DESIGNED JJC	REVISED -
\\132-3928.nokomis_rd_bridges\dgn\QUANTITIES.dgn		DRAWN UJ	REVISED -
	PLOT SCALE = 15,0000' / IN.	CHECKED MAR	REVISED -
	PLOT DATE = 9/15/2009	DATE 9-14-2009	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
723	08-00129-00-BR	MONTGOMERY	18	3
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT			CONTRACT NO. 3498	

QUANTITIES.dgn 9/15/2009 3:07:36 PM