

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY 1000	NON-PARTICIPATING Y060
60500040	REMOVING MANHOLES	EACH	4	
60500060	REMOVING INLETS	EACH	21	
* 60600605	CONCRETE CURB, TYPE B	FOOT	126	
* 60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	4,950	
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	2	
61133200	FIELD TILE JUNCTION VAULTS, 3' DIA.	EACH	2	
61139800	STORM SEWERS, SPECIAL 4"	FOOT	100	
61139900	STORM SEWERS, SPECIAL 6"	FOOT	100	
61140000	STORM SEWERS, SPECIAL 8"	FOOT	100	
61140100	STORM SEWERS, SPECIAL 10"	FOOT	100	
67100100	MOBILIZATION	L SUM	1	
* 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	
△ 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	407	
△ 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	315	
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	
* X5510100	STORM SEWER REMOVAL	FOOT	471	
* XX000300	CONCRETE STEPS	SQ FT	89	
△ * XX000731	CASING PIPE	FOOT		21
△ * XX000836	PRESSURE TESTING AND DISINFECTION	L SUM		1
△ * XX001490	GATE VALVES, 8"	EACH		5
* XX002134	CONCRETE CURB AND GUTTER OUTLET SPECIAL	EACH	2	
△ * XX003531	WATER SERVICE CONNECTION 1"	EACH		45
△ * XX003543	DUCTILE IRON WATER MAIN FITTINGS, 8" - 45 DEGREE BEND	EACH		6
* XX005293	CONCRETE HEADER BAND	FOOT	26	
* XX000406	BRICK PAVER REMOVAL AND REPLACEMENT	SQ FT	243	
△ * XX006536	WATER SERVICE LINE 1", BORED	FOOT		1,350
△ * XX008196	TRENCH BACKFILL, WATERMAIN <i>SPECIAL</i>	FOOT		1,359
△ * X0323820	DUCTILE IRON WATER MAIN TEE, 8" X 8"	EACH		1
△ * XX008210	HORIZONTAL DIRECTIONAL DRILL, 8" WATERMAIN	FOOT		105
△ * XX004731	CONNECTION TO EXISTING WATERMAIN	EACH		2

CONSTRUCTION TYPE CODE: Y007

△ SPECIALTY ITEM
* SPECIAL PROVISION

0081364_Sum.dgn
 9/29/09 10:01:50 AM
 9/29/09 10:01:50 AM
 9/29/09 10:01:50 AM

FILE NAME = 0081364_Sum.dgn	USER NAME = Quart	DESIGNED - PSA DRAWN - JTC	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CITY OF HAVANA - BROADWAY STREET	F.A. RTE.	SECTION 05-00035-00-SS	COUNTY MASON	TOTAL SHEETS 60	SHEET NO. 3
PLT SCALE =	PLT DATE = 9/29/09 10:01:50 AM	CHECKED - ERB/RDY DATE - 09/29/09	REVISED - REVISED -			SCALE: N.T.S.	SHEET NO. OF SHEETS	STA. 10+37 TO STA. 55+75	CONTRACT NO. 93502	