

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
748	06-00053-00 RS	JERSEY	110	11
STA. NA		TO STA. NA		
CONTRACT #97375		PROJECT NO. RS-0748(109)		

EARTHWORK				
LOCATION	EARTH EXCAVATION (C)	EMBANKMENT (F)	EARTH EXCAVATION ADJUSTED FOR SHRINK AGE (15%)	EARTHWORK BALANCE SHORTAGE (-) WASTE (+)
	CU. YD.	CU. YD.	CU. YD.	CU. YD.
DELHI ROAD				
STA. 157+50 TO STA. 161+50	269	408	228	-180
STA. 161+50 TO STA. 166+50	301	148	255	108
STA. 166+50 TO STA. 171+50	319	171	271	100
STA. 171+50 TO STA. 176+50	458	284	389	105
STA. 176+50 TO STA. 181+50	256	333	218	-116
STA. 181+50 TO STA. 186+50	535	263	455	192
STA. 186+50 TO STA. 191+50	478	377	406	29
STA. 191+50 TO STA. 196+50	423	295	359	64
STA. 196+50 TO STA. 201+50	593	250	504	254
STA. 201+50 TO STA. 206+50	1337	304	1137	833
STA. 206+50 TO STA. 211+50	493	258	419	161
STA. 211+50 TO STA. 216+50	394	211	335	124
STA. 216+50 TO STA. 221+50	355	155	302	146
STA. 221+50 TO STA. 226+50	374	164	318	154
STA. 226+50 TO STA. 231+50	522	227	443	216
STA. 231+50 TO STA. 236+50	714	384	607	223
STA. 236+50 TO STA. 241+50	1301	165	1106	941
STA. 241+50 TO STA. 246+50	3978	434	3381	2947
STA. 246+50 TO STA. 251+50	191	893	163	-730
STA. 251+50 TO STA. 256+50	176	1083	150	-933
STA. 256+50 TO STA. 261+50	1177	1339	1000	-339
STA. 261+50 TO STA. 266+50	1488	1373	1285	-108
STA. 266+50 TO STA. 271+50	1301	387	1105	719
STA. 271+50 TO STA. 276+50	1441	154	1225	1071
STA. 276+50 TO STA. 281+50	442	213	376	163
STA. 281+50 TO STA. 285+10	516	231	439	208
HALE LANE				
STA. 400+00 TO STA. 404+11	374	3393	318	-3075
<b>TOTAL</b>	<b>20,206</b>	<b>13,897</b>	<b>17,175</b>	<b>3,278</b>

\* NOTE: "-" INDICATES A SHORTAGE OF MATERIAL AND A NEED FOR FILL OR EMBANKMENT WHICH WILL BE ACCOUNTED FOR IN THE FURNISHED EXCAVATION QUANTITY

REVISIONS	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULES**

DELHI ROAD  
F.A.S. ROUTE 748  
SECTION 06-00053-00-RS  
JERSEY COUNTY