

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION CONSTRUCTION TYPE CODE	UNIT	90/10 FED/ST WILLIAMSON COUNTY	
			URBAN	ROADWAY
			TOTAL QUANTITY	I 000
81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	177	177
81021560	CONDUIT, AUGERED 2 1/2" DIA., PVC	FOOT	234	234
81021570	CONDUIT, AUGERED 3" DIA., PVC	FOOT	406	406
81021580	CONDUIT, AUGERED 3 1/2" DIA., PVC	FOOT	93	93
81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	71	71
81400100	HANDHOLE	EACH	16	16
81500100	GULFBOX JUNCTION	EACH	4	4
81603000	UNIT DUCT, 600V, 2-1C NO. 8, <sup>(NA 8 GROUND,</sup> 1/C (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	6839	6839
81700315	ELECTRIC CABLE IN CONDUIT, 600V (EPR- TYPE RHW) 3-1/C NO. 10	FOOT	1191	1191
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	7769	7769
82104000	LUMINAIRE, SODIUM VAPOR, MULTIMOUNT, 400 WATT	EACH	24	24
82500520	LIGHTING CONTROLLER TYPE CB-RCS 60AMP - 480VOLT	EACH	1	1
82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	3	3
83060840	LIGHT POLE, GALVANIZED STEEL, 50 FT. M.H., TENON MOUNT	EACH	22	22
* 83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8"	EACH	22	22
83800650	BREAKWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	88	88
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	5	5
84200700	LIGHTING FOUNDATION REMOVAL	EACH	5	5
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1	1
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	3	3
86000100	MASTER CONTROLLER	EACH	1	1
86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	3	3
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2230	2230
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1368	1368
87301265	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 9C	FOOT	832	832
87301275	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 12C	FOOT	1831	1831
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	7355	7355
87502310	TRAFFIC SIGNAL POST, PAINTED STEEL 16 FT.	EACH	4	4
87700120	STEEL MAST ARM ASSEMBLY AND POLE, 16 FT.	EACH	2	2
87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT.	EACH	3	3
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12	12
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	9	9
87800400	CONCRETE FOUNDATION, TYPE E, 30-INCH DIAMETER	FOOT	20	20
87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	75	75

\* SPECIALTY ITEM

FILE NAME =	USER NAME = shepardgd	DESIGNED - ---	REVISED - ---	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et\pwwork\PWIDOT\SHEPARDGD\dms47338\F	dstml3-sht-schedule.dgn	DRAWN - ---	REVISED - ---			331	(1-2)N-2,R;(1X-1)N-3,R-2	WILLIAMSON	202	8	
PLOT SCALE = 50,0000' / IN.	CHECKED - ---	REVISED - ---	REVISED - ---			CONTRACT NO. 98857					
PLOT DATE = 10/14/2009	DATE - ---	REVISED - ---	REVISED - ---			ILLINOIS FED. AID PROJECT					