

PAVEMENT MARKING SCHEDULE (WESTBOUND IL 13)

STATION TO STATION	LOCATION	POLYUREA PAVEMENT MARKING					THERMOPLASTIC PAVEMENT MARKING					PAVEMENT MARKING REMOVAL SQ FT	PAVEMENT MARKING TAPE TYPE III		
		LINE 4" WHITE	LINE 4" YELLOW	LINE 12" WHITE	LINE 24" WHITE	LETTERS & SYMBOLS WHITE	LINE 4" WHITE	LINE 4" YELLOW	LINE 12" WHITE	LINE 24" WHITE	LETTERS & SYMBOLS WHITE		LINE 4" WHITE	LINE 12" WHITE	LETTERS & SYMBOLS WHITE
		FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	SQ FT		FOOT	FOOT	SQ FT
WESTBOUND IL 13															
WB 630+50.0 TO 635+00.0	HATCHING IN FUTURE RIGHT TURN LANE														307.4
WB 630+50.0 TO 733+93.5	SKIP-BETWEEN OUTSIDE AND CENTER LANES	2585.9													
WB 630+50.0 TO 733+93.5	REFRESH SKIP BETWEEN INSIDE AND CENTER LANES														
WB 630+50.0 TO 635+12.3	OUTSIDE EDGE OF PAVEMENT														
WB 635+12.3 TO 660+27.6	OUTSIDE EDGE OF PAVEMENT	2515.3													
WB 630+67.8 TO 631+25.3	"ARROW"-RIGHT TURN LANE														20.8
WB 632+57.7 TO 660+56.3	"ONLY"-RIGHT TURN LANE														15.6
WB 632+57.7 TO 660+56.3	REFRESH INSIDE EDGE OF PAVEMENT									2798.6					932.9
WB 635+72.7 TO 636+29.1	"ARROW"-RIGHT TURN LANE														20.8
WB 636+29.1 TO 636+29.1	"ONLY"-RIGHT TURN LANE														15.6
WB 656+65.3 TO 691+40.0	INSIDE EDGE OF PAVEMENT														1158.2
WB 660+71.5 TO 660+71.5	STOP BAR-RIGHT TURN LANE ON SB TERMINAL														
WB 660+63.5 TO 660+93.5	NW ISLAND	106.9			73.6										
WB 660+88.4 TO 660+88.4	"ARROW"-SB TERMINAL RIGHT TURN LANE														20.8
WB 660+88.4 TO 660+88.4	"ONLY"-SB TERMINAL RIGHT TURN LANE														15.6
WB 660+99.0 TO 660+99.0	"ARROW"-SB TERMINAL LEFT TURN LANE														20.8
WB 660+99.0 TO 660+99.0	"ONLY"-SB TERMINAL LEFT TURN LANE														15.6
WB 660+81.5 TO 661+00.0	SB TERMINAL RT EDGE OF PAVEMENT	223.3													
WB 661+00.0 TO 661+00.0	STOP BAR-SB TERMINAL LEFT TURN LANE														
WB 661+17.5 TO 661+50.6	NE ISLAND	111.9			82.9										
WB 661+19.5 TO 661+19.5	NB TERMINAL EDGE OF PAVEMENT	133.7													
WB 661+40.5 TO 661+40.5	STOP BAR-RIGHT TURN LANE														
WB 660+93.5 TO 661+05.5	SB TERMINAL BETWEEN RTL AND LTL	133.7													
WB 661+05.5 TO 661+05.5	LINE BETWEEN SB LTL AND NB LANE														
WB 661+50.6 TO 664+63.5	LINE BETWEEN RTL AND OUTSIDE THRU LANE	312.9													
WB 664+02.3 TO 664+02.3	"ARROW"-RIGHT TURN LANE														20.8
WB 664+60.3 TO 664+60.3	"ONLY"-RIGHT TURN LANE														15.6
WB 661+68.8 TO 707+68.4	OUTSIDE EDGE OF PAVEMENT	4599.6													
WB 661+85.7 TO 661+85.7	STOP BAR-THREE THRU LANES														
WB 661+85.7 TO 666+35.2	INSIDE EDGE OF PAVEMENT														
WB 670+60.5 TO 688+05.8	MEDIAN HATCHING	1745.3			522.4										
WB 670+60.5 TO 675+55.2	RT EDGE OF ACCELERATION LANE	494.7													
WB 682+38.5 TO 682+38.5	STOP BAR-DECELERATION LANE														
WB 683+48.7 TO 683+48.7	"ARROW"-DECELERATION LANE														20.8
WB 684+05.0 TO 684+05.0	"ONLY"-DECELERATION LANE														15.6
WB 685+24.6 TO 688+05.8	RT EDGE OF DECELERATION LANE	281.2													
WB 686+19.6 TO 691+40.0	LT EDGE OF DECELERATION LANE														520.4
WB 687+38.7 TO 687+38.7	"ARROW"-DECELERATION LANE														20.8
WB 687+96.9 TO 687+96.9	"ONLY"-DECELERATION LANE														15.6
WB 691+40.0 TO 708+25.0	REFRESH INSIDE EDGE OF PAVEMENT														
WB 708+13.5 TO 708+13.5	STOP BAR-REDCO RT TURN LANE														
WB 708+02.5 TO 708+51.2	NW ISLAND	174.6			79.0										
WB 708+51.2 TO 708+51.2	LINE BETWEEN REDCO SB THRU AND RTL	32.7													
WB 708+63.9 TO 708+63.9	LINE BETWEEN REDCO SB THRU AND LTL	76.0													
WB 708+75.5 TO 708+75.5	LINE BETWEEN REDCO NB THRU AND SB LTL														150.0
WB 708+57.5 TO 708+57.5	STOP BAR-SB REDCO THRU LANE														12.0
WB 708+68.7 TO 708+68.7	STOP BAR-SB REDCO LT TURN LANE														12.0
WB 708+93.3 TO 709+46.2	NE ISLAND	174.7			97.3										
WB 709+07.5 TO 709+07.5	STOP BAR-THREE THRU LANES														12.0
WB 709+07.5 TO 711+51.5	REFRESH LINE BETWEEN IN LANE AND OUT LTL														244.0
WB 709+35.7 TO 713+47.0	REFRESH INSIDE EDGE OF PAVEMENT														411.3
WB 713+47.0 TO 733+93.5	REFRESH INSIDE EDGE OF PAVEMENT														
WB 709+46.2 TO 712+65.0	LINE BETWEEN RTL AND OUT THRU LANE	318.8													
WB 709+50.2 TO 709+50.2	STOP BAR-LEFT TURN LANES														
WB 709+50.2 TO 711+51.5	REFRESH LINE BETWEEN IN AND OUT LTL														
WB 710+25.8 TO 710+25.8	"ARROW"-RIGHT TURN LANE														20.8
WB 710+52.1 TO 710+52.1	"ONLY"-RIGHT TURN LANE														15.6
WB 710+78.8 TO 710+78.8	"ARROW"-LEFT TURN LANE														20.8
WB 710+78.8 TO 710+78.8	"ARROW"-LEFT TURN LANE														20.8
WB 711+36.3 TO 711+36.3	"ONLY"-LEFT TURN LANE														15.6
WB 711+36.3 TO 711+36.3	"ONLY"-LEFT TURN LANE														15.6
WB 709+62.4 TO 733+93.5	OUTSIDE EDGE OF PAVEMENT	2431.1													
WB 731+56.2 TO 733+93.5	HATCHING														
SUBTOTALS		16452.3	1842.6	855.2	165.0	218.4	2829.9	6731.4	0.0	36.0	72.8	4466.1	699.6	369.8	72.8