

# TEMPORARY PAVEMENT MARKING SCHEDULE

## (EASTBOUND IL 13)

STATION TO STATION	LOCATION	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING					SHORT TERM PAVEMENT MARKING
			LINE 4" WHITE	LINE 4" YELLOW	LINE 12" WHITE	LINE 24" WHITE	LETTERS & SYMBOLS WHITE	
			SQ FT	FOOT	FOOT	FOOT	FOOT	
<b>EASTBOUND IL 13</b>								
PENTECOST		ADDITIONAL QUANTITY FOR STAGING	127.0	165			36	
BAINBRIDGE		ADDITIONAL QUANTITY FOR STAGING	241.3	400			54	
		SHORT TERM QUANTITY						1324
WB 631+25.0 TO 732+37.0		HATCHING IN FUTURE MERGE LANE	529.1		529.1			
EB 631+35.0 TO 639+00.0		SKIP BETWEEN OUTSIDE AND CENTER LANES	841.8	2525.5				
EB 631+35.0 TO 732+37.0		REFRESH SKIP BETWEEN INSIDE AND CENTER LANES	841.8	2525.5				
EB 631+35.0 TO 651+46.0		REFRESH LT EDGE OF PAVEMENT	670.3		2011.0			
EB 631+35.0 TO 681+12.0		OUTSIDE EDGE OF PAVEMENT AND RT. TURN LANE	1659.0	4977.0				
EB 651+46.0 TO 686+19.6		LT EDGE OF PAVEMENT	0.0					
EB 654+75.0 TO 672+10.5		HATCHING IN MEDIAN	1046.5	1735.5		468.0		
EB 651+46.0 TO 656+65.0		LT EDGE OF DECELERATION LANE	173.0	0.0	519.0			
EB 654+75.0 TO 657+61.1		RT EDGE OF DECELERATION LANE	95.4	286.1				
EB 654+65.0		"ONLY"-DECELERATION LANE	20.7				20.7	
EB 655+21.0		"ARROW"-DECELERATION LANE	15.8				15.8	
EB 658+65.0		"ONLY"-DECELERATION LANE	20.7				20.7	
EB 659+21.0		"ARROW"-DECELERATION LANE	15.8				15.8	
EB 660+46.0		STOP BAR-DECELERATION LANE	28.0			14.0		
EB 667+31.0 TO 672+10.5		RIGHT EDGE OF ACCELERATION LANE	159.8	479.5				
EB 677+52.0 TO 680+84.0		LEFT EDGE OF PAVEMENT	110.7		332.0			
EB 678+12.0 TO 681+27.0		LEFT EDGE OF RIGHT TURN LANE	105.0	315.0				
EB 678+18.0		"ONLY"-RIGHT TURN LANE	20.7				20.7	
EB 678+75.0		"ARROW"-RIGHT TURN LANE	15.8				15.8	
EB 681+00.0		STOP BAR-THREE THRU LANES	74.0			37.0		
EB 681+27.0 TO 681+68.0		SW ISLAND	166.1	140.0		119.4		
EB 681+34.0		STOP BAR-RT TURN LANE	28.0			14.0		
EB 681+80.0		BETWEEN NB AND SB PENTECOST	38.2		114.5			
EB 681+86.0		STOP BAR-NB PENTECOST	24.0			12.0		
EB 681+92.0 TO 682+33.0		SE ISLAND	161.7	149.0		112.0		
EB 682+23.0		STOP BAR-RT TURN LANE PENTECOST	36.0			18.0		
EB 682+25.0 TO 686+19.6		LEFT EDGE OF PAVEMENT	131.5		394.6			
EB 682+66.6 TO 707+60.0		RT EDGE OF PAVEMENT AND RT TURN LANE	831.1	2493.4		0.0		
EB 686+19.6 TO 708+24.8		REFRESH LT EDGE OF PAVEMENT	735.1		2205.2			
EB 703+98.0 TO 708+26.2		RT SIDE OF LEFT TURN LANE	142.7	428.2				
EB 704+11.0		"ONLY"-LEFT TURN LANE	20.7				20.7	
EB 704+69.0		"ARROW"-LEFT TURN LANE	15.8				15.8	
EB 704+55.0 TO 707+75.0		LEFT EDGE LINE OF RIGHT TURN LANE	106.7	320.0			0.0	
EB 704+70.0		"ONLY"-RIGHT TURN LANE	20.7				20.7	
EB 704+96.0		"ARROW"-RIGHT TURN LANE	15.8				15.8	
EB 706+09.8		"ONLY"-LEFT TURN LANE	20.7				20.7	
EB 706+67.0		"ARROW"-LEFT TURN LANE	15.8				15.8	
EB 706+70.0		"ONLY"-RIGHT TURN LANE	20.7				20.7	
EB 706+95.0		"ARROW"-RIGHT TURN LANE	15.8				15.8	
EB 707+86.0 TO 708+18.5		HATCHING BETWEEN INSIDE THRU AND LEFT TURN LANES	44.3	39.9		31.0		
EB 708+16.5		STOP BAR-LEFT TURN LANE	28.0			14.0		
EB 708+25.7		STOP BAR-THREE THRU LANES	72.0			36.0		
EB 708+19.5		STOP BAR-RIGHT TURN LANE	36.0			18.0		
EB 707+72.8 TO 708+46.9		SW ISLAND	258.4	260.0		171.7		
EB 708+59.0		BETWEEN TWO SB BAINBRIDGE LANES	24.3	73.0				
EB 708+82.0		STOP BAR-NB BAINBRIDGE INSIDE THRU LANE	24.0			12.0		
EB 708+93.0		STOP BAR-NB BAINBRIDGE OUTSIDE THRU LANE	24.0			12.0		
EB 708+98.8 TO 709+47.4		SE ISLAND	144.1	174.2		86.0		
EB 709+36.4		STOP BAR-RT TURN LANE BAINBRIDGE	36.0			18.0		
EB 709+81.5 TO 732+37.0		RIGHT EDGE OF PAVEMENT	751.8	2255.5				
EB 709+35.7 TO 729+37.1		REFRESH LT EDGE OF PAVEMENT	667.1		2001.4			
EB 729+90.0 TO 732+37.0		HATCHING IN FUTURE RIGHT TURN LANE	128.2			128.2		
EB 663+95.6		LEFT TURN LANE	15.8				15.8	
EB 664+52.2		LEFT TURN LANE	20.7				20.7	
<b>SUBTOTALS</b>			<b>11634</b>	<b>19742</b>	<b>7578</b>	<b>1645</b>	<b>295</b>	<b>1324</b>
<b>TOTALS</b>			<b>22979</b>	<b>55429</b>	<b>2774</b>	<b>554</b>	<b>621</b>	<b>2678</b>