

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				80% FEDERAL 20% STATE	
				ROADWAY 0005	RURAL
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	15,876	15876	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	2,101	2101	
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	23,814	23814	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	374	374	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	116	116	
44000600	SIDEWALK REMOVAL	SQ FT	355	355	
44002235	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 8 3/4"	SQ YD	800	800	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	17,860	17860	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1,018	1018	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	94	94	
54260515	SLOPED METAL END SECTION, STANDARD 542411, 15", 1:6	EACH	2	2	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	118	118	
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	15,860	15860	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	

* SPECIALTY ITEM



MODEL: Default
FILE: \\nrcs-pub\pubroom\dat\illinois.gov\PWIDOT\Documents\DOT_Offices\Illinrcs\2\Projects\0205611\CADDData\CAD\Sheet\0205611-ph-500.dgn

USER NAME = oterod	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 40:0 ** / in.	CHECKED -	REVISED -
PLOT DATE = Oct-08-2020 12:31:19 PM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF
QUANTITIES**

SCALE: SHEET 2 OF 3 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
223	101RS-4	HENRY	27	5
			CONTRACT NO. 64G94	
		ILLINOIS	FED. AID PROJECT	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				80% FEDERAL	20% STATE
				ROADWAY	
				0005	
				RURAL	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	8,243	8,243	
70102621	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	916	916	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	46,484	46,484	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	82	82	
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	229	229	
Z0004542	HOT-MIX ASPHALT REMOVAL (SPECIAL)	SQ YD	993	993	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
* Z0025505	PROPERTY MARKERS	EACH	5	5	
Z0033700	LONGITUDINAL JOINT SEALANT	FOOT	8,930	8,930	



* SPECIALTY ITEM

MODEL: Default
FILE: \\harris-pc\pub\harris\mtdat\illinois.gov\PW\DOT\Documents\DOT_Offices\District 2\Projects\ID20561\1\CADData\CAD\Sheet\ID20561-1-rh-500.dgn

USER NAME = oterod	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 40:0 ** / in.	CHECKED -	REVISED -
PLOT DATE = Oct-08-2020 12:31:31 PM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF
QUANTITIES**

SCALE: SHEET 3 OF 3 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
223	101RS-4	HENRY	27	6
CONTRACT NO. 64G94				
ILLINOIS FED. AID PROJECT				