

PROJECT: 0464001  
 FILE: 0464001.dwg  
 USER: jshannon  
 DATE: 10/27/2020  
 PLOT SCALE: 1/8" = 1'-0"  
 PLOT DATE: 10/27/2020

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0005 SHELBY	0005 MACON
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD	L SUM	1	0.9	0.1
	701401				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD	L SUM	1	0.9	0.1
	701701				
70107006	PAVEMENT MARKING BLACKOUT TAPE, 6"	FOOT	650	325	325
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	28	27.5	0.5
70300100	SHORT TERM PAVEMENT MARKING	FOOT	15584	14166	1418
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SO FT	2922	2523	399
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	1362	1237	125
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	103260	93719	9541
72501000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1362	1237	125
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	103260	93719	9541
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2691	2503	188
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1670	1579	91

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0005 SHELBY	0005 MACON
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	152	137	15
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	616	616	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	699	641	58
78200005	GUARDRAIL REFLECTORS, TYPE A	EACH	10	10	
<del>X7050167</del>	<del>TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)</del>	<del>EACH</del>	<del>4</del>	<del>4</del>	
X7830060	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS AND SYMBOLS	SO FT	1362	1237	125
X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	103260	93719	9541
X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	2691	2503	188
X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	1670	1579	91
X7830090	GROOVING FOR RECESSED PAVEMENT MARKING 25"	FOOT	152	137	15
Z0033700	LONGITUDINAL JOINT SEALANT	FOOT	64735	59363	5372
Z0049799	PROTECTING OR RESETTING SURVEY MARKERS	EACH	9	6	3
Z0070202	SURVEY MARKER VAULT	EACH	2	2	

△ REV. 12-14-2020

USER NAME = Qltmarinos	DESIGNED -	REVISED -
PLOT SCALE = 1/8" = 1'-0"	DRAWN -	REVISED -
PLOT DATE = 10/27/2020	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE. 322/322A	SECTION 146.47RS-3	COUNTY SHELBY/MACON	TOTAL SHEETS 33	SHEET NO. 4
CONTRACT NO. 74549			ILLINOIS FED. AID PROJECT	