



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 5, 2021

SUBJECT: FAU Route 7706 (Lincoln Parkway)
Project STP-5UU5(557)
Section (22)BDR
Logan County
Contract No. 72L96
Item No. 77, January 15, 2021 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page i of the Table of Contents to the Special Provisions.
3. Revised page 4 of the Special Provisions.
4. Revised sheet 3 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
TRAFFIC CONTROL PLAN	1
STATUS OF UTILITIES TO BE ADJUSTED	2
TRAFFIC CONTROL AND PROTECTION, (SPECIAL).....	3
PAVEMENT STATIONING NUMBERS AND PLACEMENT	3
DRAINAGE SCUPPERS TO BE ADJUSTED	4
RAILROAD PROTECTIVE LIABILITY INSURANCE (5 AND 10) (BDE).....	5
WIDTH RESTRICTION AND MAXIMUM WIDTH SIGNING	6
BRIDGE DECK MICROSILICA CONCRETE OVERLAY.....	6
QC/QA OF CONCRETE MIXTURES APPLICABLE ITEMS.....	7
DECK SLAB REPAIR.....	7
BRIDGE DECK MICROSILICA CONCRETE OVERLAY	12
COMPENSABLE DELAY COSTS (BDE)	22
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	25
DISPOSAL FEES (BDE).....	33
EMULSIFIED ASPHALTS (BDE)	34
ENGINEER’S FIELD OFFICE AND LABORATORY (BDE).....	37
HOT-MIX ASPHALT – BINDER AND SURFACE COURSE (BDE)	39
HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (MODIFIED FOR I-FIT) (BDE).....	46
MOBILIZATION (BDE).....	49
PORTLAND CEMENT CONCRETE – HAUL TIME (BDE)	50
PORTLAND CEMENT CONCRETE BRIDGE DECK CURING (BDE).....	51
RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (BDE).....	52
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)	61
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE).....	70
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....	71
TEMPORARY PAVEMENT MARKING (BDE).....	71
TRAFFIC CONTROL DEVICES - CONES (BDE).....	73
TRAINING SPECIAL PROVISIONS (BDE)	74
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION...76	

DRAINAGE SCUPPERS TO BE ADJUSTED

Description:

This work shall consist of all material and labor required to adjust inlets to match the proposed HMA surface and to install bolt down grates as specified on Standard 610001

Construction Requirements:

The Contractor shall remove the existing castings and grates, remove concrete around the casting as specified in the plan detail, build up the inlet with polymer concrete, and set new casting and grate.

Materials:

Materials shall meet the requirements of the Recurring Special Provision #16 POLYMER CONCRETE. The contractor shall supply new frames and grates as detailed on Standard 610001 and specified in Article 1006.14 of the Standard Specifications.

Method of Measurement:

This work shall be measured for payment in units of each, at locations specified. Polymer concrete will not be paid for separately but included in this item of work.

Basis of Payment:

This work will be paid for at the contract unit price per each for DRAINAGE SCUPPERS TO BE ADJUSTED

Revised January 5, 2021