

MODEL: Default  
 FILE: \\nls1c1-pix\pub\room\dat\illinois.gov\PIWDOT\Documents\DOT\_Offices\District\_8\Projects\ID276M85\CADD\Drawn\CAD\Drawn\ID276M85-shc-cover.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				80% FED 20% STATE ROADWAY 0005 RURAL
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	60	60
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2293	2293
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	764	764
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2293	2293
70400100	TEMPORARY CONCRETE BARRIER	FOOT	137.5	137.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	137.5	137.5
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2293	2293
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	42	42
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	115	115

\* SPECIALTY ITEM

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				80% FED 20% STATE ROADWAY 0005 RURAL
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	115	115
<del>X0324762</del>	<del>WIDE LOAD DETOUR SIGNING</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>
X0900064	MEMBRANE WATERPROOFING SYSTEM FOR BURIED STRUCTURES	SQ YD	43.4	43.4
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	55.7	55.7
X4421021	CLASS B PATCHES, TYPE IV, 12 INCH, SPECIAL	SQ YD	43.4	43.4
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT	764	764
X7040125	PINNING TEMPORARY CONCRETE BARRIER	EACH	54	54
X7200200	WIDE LOAD SIGNING	L SUM	1	1
∅ Z0076600	TRAINEES	HOUR	1500	1500
Z0033700	LONGITUDINAL JOINT SEALANT	FOOT	9169	9169
∅ Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	1500	1500
Z0034105	MATERIAL TRANSFER DEVICE	TON	5135	5135

∅ 0042

△ REV. 12-16-2020

REV. - MS

USER NAME = millerraj	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
DRAWN -	REVISIED -	785				(137-2,138,139)RS-4	MADISON	14	4	
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISIED -				CONTRACT NO. 76M85				
PLOT DATE = 10/6/2020	DATE -	REVISIED -				SCALE:	SHEET 1 OF 1 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT	