

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAI Routes 57 & 70
D5-7 OVD SIN STR REPL 2009-5
Various Counties
Sheet 5 of 35
Contract Number 46006

Schedule of Overhead Sign Structure Replacement

Location No.:	5-01	State I.D. No.:	5S010I057R235.3		
County:	Champaign	Route:	I - 57	M.P.:	235.3
				Direction:	NB
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE - SPAN		EACH	1.00		
OVERHEAD SIGN STRUCTURE-SPAN TYPE II-A		FOOT	81.00		
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE		EACH	2.00		
DRILLED SHAFT CONCRETE FOUNDATION		CU YD	21.50		
REMOVE CONCRETE FOUNDATION OVERHEAD		EACH	2.00		
DISCONNECT/RECONNECT ELECTRIC SERVICE		EACH	1.00		
RELOCATE ELECTRIC SERVICE		EACH	1.00		
REMOVE & REINSTALL SIGN PANEL		SQ FT	645.00		
REMOVE & REINSTALL WALKWAY		FOOT	48.00		
REPAIR HANDRAIL LOCKING PIN CONNECTION		EACH	5.00		
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00		
PAVED DITCH REMOVAL & REPLACEMENT		FOOT	40.00		
CHANGEABLE MESSAGE SIGN		CAL DAY	35.00		
This overhead sign structure is being completely replaced.					

Location No.:	5-02	State I.D. No.:	5S010I057L236.0		
County:	Champaign	Route:	I - 57	M.P.:	236.0
				Direction:	SB
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE - SPAN		EACH	1.00		
OVERHEAD SIGN STRUCTURE-SPAN TYPE I-A		FOOT	88.00		
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE		EACH	2.00		
DRILLED SHAFT CONCRETE FOUNDATION		CU YD	26.30		
REMOVE CONCRETE FOUNDATION OVERHEAD		EACH	2.00		
DISCONNECT/RECONNECT ELECTRIC SERVICE		EACH	1.00		
RELOCATE ELECTRIC SERVICE		EACH	1.00		
REMOVE & REINSTALL SIGN PANEL		SQ FT	217.00		
REMOVE & REINSTALL WALKWAY		FOOT	31.00		
REPAIR HANDRAIL LOCKING PIN CONNECTION		EACH	4.00		
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00		
CHANGEABLE MESSAGE SIGN		CAL DAY	35.00		
IMPACT ATTENUATORS (NON-REDIRECTIVE) TL3		EACH	2.00		
ATTENUATOR BASE		SQ YD	102.00		
IMPACT ATTENUATOR REMOVAL		EACH	2.00		
GUARD POST		EACH	35.00		
GUARD POST REMOVAL		EACH	23.00		
This overhead sign structure is being completely replaced.					

Rev.