

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAI Routes 57 & 70
D5-7 OVD SIN STR REPL 2009-5
Various Counties
Sheet 20 of 35
Contract Number 46006

Schedule of Overhead Sign Structure Replacement

Location No.:	7-01	State I.D. No.:	7S015I057L189.9		
County:	Coles	Route:	I - 57	M.P.:	189.9
				Direction:	SB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00			
OVERHEAD SIGN STRUCTURE - SPAN, TYPE I A	FOOT	96.00			
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	20.50			
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00			
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00			
REMOVE & REINSTALL SIGN PANEL	SQ FT	270.50			
REMOVE & REINSTALL WALKWAY	FOOT	51.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	12.00			
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00			
RELOCATE ELECTRIC SERVICE	EACH	1.00			
This structure is being completely replaced.					

Location No.:	7-02	State I.D. No.:	7S025I057R161.3		
County:	Effingham	Route:	I - 57	M.P.:	161.3
				Direction:	NB
Description of Work	Unit	Quantity			
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00			
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00			
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	4.00			
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00			
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	89.00			
REPLACE / TIGHTEN CLIP PER SIGN	EACH	2.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	12.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00			
<i>Work to be completed between 11:00pm and 7:00 am</i>					
Replace Existing End Supports.					
Existing plans show end supports as 10-inch columns.					

Location No.:	7-03	State I.D. No.:	7S025I057R162.9		
County:	Effingham	Route:	I - 57	M.P.:	162.9
				Direction:	NB
Description of Work	Unit	Quantity			
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00			
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00			
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	4.00			
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00			
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	88.00			
REPLACE / TIGHTEN CLIP PER SIGN	EACH	1.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	8.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00			
<i>Work to be completed between 11:00pm and 7:00 am</i>					
Replace Existing End Supports.					
Existing plans show end supports as 10-inch columns.					

Location No.:	7-04	State I.D. No.:	7S025I070L099.0		
County:	Effingham	Route:	I - 70	M.P.:	99
				Direction:	WB
Description of Work	Unit	Quantity			
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00			
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00			
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	4.00			
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00			
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	89.00			
REPLACE / TIGHTEN CLIP PER SIGN	EACH	2.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	3.00			
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
Replace Existing End Supports.					
Existing plans show end supports as 10-inch columns.					

Location No.:	7-05	State I.D. No.:	7S025I057L164.3		
County:	Effingham	Route:	I - 57	M.P.:	164.3
				Direction:	SB
Description of Work	Unit	Quantity			
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00			
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00			
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	4.00			
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00			
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	89.00			
TIGHTEN U-BOLT	EACH	2.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	8.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00			
Replace Existing End Supports.					
Existing plans show end supports as 10-inch columns.					

Location No.:	7-06	State I.D. No.:	7S025I057L163.8		
County:	Effingham	Route:	I - 57	M.P.:	163.8
				Direction:	SB
Description of Work	Unit	Quantity			
REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE - SPAN	EACH	1.00			
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00			
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	4.00			
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00			
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	103.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	12.00			
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00			
Replace Existing End Supports.					
Existing plans show end supports as 10-inch columns.					

Rev.