

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	99-1-B-1-2	WILL	21	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT NO. 60D66

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SFTY-2A				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	87	87				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	57.6	57.6				
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SO YD	476	476				
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	786	786				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	10	10				
50102400	CONCRETE REMOVAL	CU YD	76	76				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	84.5	84.5				
50300260	BRIDGE DECK GROOVING	SO YD	2597	2597				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	17560	17560				
50800515	BAR SPLICERS	EACH	84	84				
52000110	PREFORMED JOINT STRIP SEAL	FOOT	264	264				
64200105	SHOULDER RUMBLE STRIP	FOOT	2140	2140				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	1				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1175	1175				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1175	1175				
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2795	2795				
* 78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	726	726				
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	40	40				
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	18	18				
* 78100300	REPLACEMENT REFLECTOR	EACH	17	17				
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	68	68				
78300100	PAVEMENT MARKING REMOVAL	SO FT	552	552				
X0320887	POLYMER CONCRETE	CU FT	9.2	9.2				
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SO YD	2558	2558				

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SFTY-2A				
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SO FT	174	174				
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	3054	3054				
X0325775	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	11,500	11,500				
X0325840	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 12 INCH	FOOT	40	40				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	70	70				
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SO YD	2558	2558				
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	9.6	9.6				
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2				
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2				
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	3	3				
X0325870	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	FOOT	880	880				

10/30/2008

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

*Specialty Items Rev.

PLOT DATE: 10/30/2008