

PAY ITEM QUANTITY SUMMARY							
ITEM NO	PAY ITEM	UNIT	TOTAL QUANTITY	STATION 0+00 - 4+50	STATION 4+50 - 10+50	STATION 10+50 - 17+00	STATION 17+00 - 21+68
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	32	0	7	6	19
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	53	36	17	0	0
20200100	EARTH EXCAVATION	CU YD	558	106	179	190	84
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	897	203	227	284	186
20700420	POROUS GRANULAR EMBANKMENT SUBGRADE	CU YD	130	32	32	32	32
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	3047	612	913	889	633
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5624	2364	1025	1355	880
25000210	SEEDING, CLASS 2A	ACRE	1.2	0.5	0.2	0.3	0.2
25100401	EXCELSIOR BLANKET, SPECIAL	SQ YD	5624	2364	1025	1355	880
28000400	PERIMETER EROSION BARRIER	FOOT	2240	487	599	835	319
28000500	INLET AND PIPE PROTECTION	EACH	4	1	0	3	0
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	2858	613	846	817	581
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	743	149	223	217	154
40603030	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	332	66	101	96	69
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	218	44	66	63	45
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4866	1315	898	941	1712
42400800	DETECTABLE WARNINGS	SQ FT	56	24	0	0	32
44000600	SIDEWALK REMOVAL	SQ FT	737	341	0	0	396
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3	0	0	3	0
60100915	PIPE DRAINS 6"	FOOT	57	0	0	57	0
60107700	PIPE UNDERDRAINS 6"	FOOT	277	0	0	29	248
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1	0	0	0	1
60251200	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 8 GRATE	EACH	1	1	0	0	0
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	126	59	0	0	67
67100100	MOBILIZATION	LS	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	LS	1				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	74	0	0	0	74
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	88	0	0	0	88
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2155	445	600	650	460
* 81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	1104				
* 81500100	GULFBOX JUNCTION	EACH	2				
* 81700110	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/0 NO. 10	FOOT	4702				
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1104				
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	105				
X0300626	CURB AND GUTTER REMOVAL	FOOT	828	729	36	0	63
X0321158	PARK BENCHES	EACH	1	0	0	0	1
* X8950130	MODIFY EXISTING LIGHTING CONTROLLER	EACH	1				
* XX000303	ORNAMENTAL LIGHTING UNIT COMPLETE	EACH	12				
XX001011	BICYCLE RACKS	EACH	5	5	0	0	0
XX006698	TREE PROTECTION AND PRESERVATION	EACH	36	1	13	12	10
* XX007745	ROTATE LIGHT FIXTURE	EACH	10	0	5	4	1
* XX007746	STEEL POLE REMOVAL	EACH	2	2	0	0	0
XX007747	PARK BENCH REMOVAL AND RELOCATION	EACH	6	0	2	2	2
XX001532	PROJECT SIGN	EACH	2	1	0	0	1

* SPECIALTY ITEMS

EXCAVATION SCHEDULE						
LOCATION	SUITABLE EXCAVATION (EARTH EXCAVATION)	EARTH EX ADJUSTED FOR SHRINKAGE (15%)	SUITABLE EMBANKMENT	EARTHWORK BALANCE WASTE(+) OR SHORTAGE (-) (FURNISHED EXCAVATION)	UNSUITABLE EXCAVATION (REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL)	UNSUITABLE EXCAVATION (TOPSOIL)
Mainline Path	CY	CY	CY	CY	CY	CY
STA. 0+00 TO 4+50	106.1	90.2	203.1	-113.0	203.0	264.6
STA. 4+50 TO 10+50	179.2	152.3	47.5	104.8	227.0	156.8
STA. 10+50 TO 17+00	189.6	161.2	16.0	145.2	281.4	164.8
STA. 17+00 TO 21+68	83.5	71.0	30.4	40.6	185.6	101.2
TOTALS	558	475	297	178	897	687

DRAINAGE SCHEDULE					
LOCATION	(60100915) PIPE DRAINS 6" (FT)	(60107700) PIPE UNDERDRAINS 6" (FT)	(60236200) INLETS, TYPE A, TYPE 8 GRATE (EACH)	(60100060) CONCRETE HEADWALL FOR PIPE DRAINS (EACH)	(60251200) CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 8 GRATE (EACH)
Mainline Path	(FT)	(FT)	(EACH)	(EACH)	(EACH)
STA. 0+00 TO 4+50					1
STA. 4+50 TO 10+50					
STA. 10+50 TO 17+00	57	29		3	
STA. 17+00 TO 21+68		248	1		
TOTALS	57	277	1	3	1

TREE REMOVAL SCHEDULE					
LOCATION	(20100110) TREE REMOVAL (6 TO 15 UNITS DIAMETER)		LOCATION	(20100210) TREE REMOVAL (OVER 15 UNITS DIAMETER)	
STATION OFFSET	NO.	DIA	STATION OFFSET	NO.	DIA
7+14, 8'L	1	7	1+94, 14'L	1	36
13+95, 1'R	1	6	5+95, 6'R	1	17
20+96, 9'L	1	12		0	0
21+19, 6'L	1	7		0	0
TOTALS		32	TOTALS		53

URS 100 S. WACKER DR., SUITE 500 TEL (312)-939-1000
CHICAGO IL, 60606 FAX (312)-939-4198

REVISIONS	
NAME	DATE

CITY OF EVANSTON
TWIGGS PARK
SUMMARY OF QUANTITIES
AND MAINLINE QUANTITIES

DATE : 6/20/08
DRAWN BY : LLM
CHECKED BY : BA