

# SUMMARY OF QUANTITIES

**CONSTR. CODE**

80% Fed  
20% State

**MINOR STRUCTURES**

Y007

S.N. 043-1027

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
20200100	EARTH EXCAVATION	CU YD	11068	11068
20200200	ROCK EXCAVATION	CU YD	100	100
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	45	45
* 25000210	SEEDING, CLASS 2A	ACRE	1.25	1.25
* 25000310	SEEDING, CLASS 4	ACRE	1	1
(: 25000750	MOWING	ACRE	2.25	2.25
* 25100115	MULCH, METHOD 2	ACRE	1.48	1.48
* 25100630	EROSION CONTROL BLANKET	SQ YD	3718	3718
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	900	900
28000300	TEMPORARY DITCH CHECKS	EACH	65	65
28000400	PERIMETER EROSION BARRIER	FOOT	261	261
28000500	INLET AND PIPE PROTECTION	EACH	2	2
28100107	STONE RIPRAP, CLASS A4	SQ YD	272	272
28200200	FILTER FABRIC	SQ YD	1101	1101
28300470	AGGREGATE DITCH 12"	SQ YD	668	668
35101400	AGGREGATE BASE COURSE, TYPE B	TON	1343	1343
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	199	199
42001200	PAVEMENT FABRIC	SQ YD	237	237
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	237	237
44213200	SAW CUTS	FOOT	238	238
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1777	1777
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1

\* SPECIALTY ITEM

(: NON PARTICIPATING 100% STATE

FILE NAME =	USER NAME = dssdd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>US 20</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
est\pw_work\PMIDOT\DOSSDD\dms34517\sl11804\evr.dgn		DRAWN -	REVISED -		<b>SUMMARY OF QUANTITIES</b>	-301	24T-5	JODAVIESS	43	3	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -		SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT			
PLOT DATE = Thu Oct 09 09:36:20 2008		DATE -	REVISED -		CONTRACT NO. 64C69						