

20200100 EARTH EXCAVATION					REMARKS
CU YD	LOCATION		OFFSET		
10834	2122+00.0 TO 2134+30	LT & RT			
	Golf Road				
234	299+00 TO 299+75	LT			Golf Road
11068	TOTAL				

20200200 ROCK EXCAVATION					REMARKS
CU YD	LOCATION		OFFSET		
100	ENTIRE JOB				TO BE USED IF NEEDED

20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL					REMARKS
CU YD	LOCATION		OFFSET		
45	2124+02.9				TO BE USED IF NEEDED

25000210 SEEDING, CLASS 2A					REMARKS
ACRE	LOCATION		OFFSET		
0.50	2122+00 TO 2134+30	LT			FORESLOPES & BOTTOM FORESLOPES & BOTTOM (includes Golf Road)
0.75	2122+00 TO 2134+75	RT			
1.25	TOTAL				

25000310 SEEDING, CLASS 4					REMARKS
ACRE	LOCATION		OFFSET		
0.50	2122+00 TO 2134+30	LT			BACKSLOPES BACKSLOPES (includes Golf Road)
0.50	2122+00 TO 2134+30	RT			
1.00	TOTAL				

25000750 MOWING					REMARKS
ACRE	LOCATION		OFFSET		
1.00	2122+00 TO 2134+30	LT			(includes Golf Road)
1.25	2122+00 TO 2134+30	RT			
2.25	TOTAL				

25100115 MULCH, METHOD 2					REMARKS
ACRE	LOCATION		OFFSET		
0.96	2122+00 TO 2134+30	LT			(includes Golf Road)
0.52	2122+00 TO 2134+30	RT			
1.48	TOTAL				

25100630 EROSION CONTROL BLANKET					REMARKS
SQ YD	LOCATION		OFFSET		
176	2123+50 TO 2124+00	LT			4' F/S BTM & B/S 4' F/S BTM & B/S
3542	2124+00 TO 2134+00	RT			
3718	TOTAL				

28000250 TEMPORARY EROSION CONTROL SEEDING					REMARKS
POUND	LOCATION		OFFSET		
900	2123+50 TO 2124+00	LT & RT			4 APPLICATIONS IF APPLICABLE

28000300 TEMPORARY DITCH CHECKS						REMARKS
EACH	LOCATION		OFFSET			
5	2121+50 TO 2123+50	LT			50' SPACING	
2	2122+50 TO 2123+00	RT			50' SPACING	
8	2123+00 TO 2124+00	RT			15' SPACING	
2	2123+50 TO 2124+00	LT			30' SPACING	
15	2124+00 TO 2131+00	LT			50' SPACING	
13	2124+00 TO 2130+00	RT			50' SPACING	
13	2130+00 TO 2133+00	RT			25' SPACING	
3	2131+00 TO 2131+50	LT			25' SPACING	
4	2133+00 TO 2133+50	RT			15' SPACING	
65	TOTAL					

28000400 PERIMETER EROSION BARRIER					REMARKS
FOOT	LOCATION		OFFSET		
261	2122+50 TO 2125+00	RT			

28000500 INLET AND PIPE PROTECTION					REMARKS
EACH	LOCATION		OFFSET		
1	2124+09	LT			
1	2134+60.85	RT			
2	TOTAL				

28100107 STONE RIPRAP, CLASS A4					REMARKS
SQ YD	LOCATION		OFFSET		
135	2123+87.5 TO 2124+25	LT			
134	2123+87.5 TO 2124+18	RT			
3	2134+60.85	RT			
272	TOTAL				

28200200 FILTER FABRIC					REMARKS
SQ YD	LOCATION		OFFSET		
135	2123+87.5 TO 2124+25	LT			UNDER RIPRAP UNDER RIPRAP UNDER AGGREGATE DITCH
134	2123+87.5 TO 2124+18	RT			
829	2124+25 TO 2131+50	LT			
3	2134+60.85	RT			
1101	TOTAL				

28300470 AGGREGATE DITCH 12"					REMARKS
SQ YD	LOCATION		OFFSET		
668	2124+25 TO 2131+50	LT			Class A3

35101400 AGGREGATE BASE COURSE, TYPE B					REMARKS
TON	LOCATION		OFFSET		
73	2122+24	LT			FE (8" THICKNESS)
645	2122+32 TO 2133+13.5	LT			
626	2122+41 TO 2133+89.5	RT			
1343	TOTAL				

40603310 HOT MIX ASPHALT SURFACE COURSE, MIX "C", N 50					REMARKS
TON	LOCATION		OFFSET		
101	2122+32 TO 2134+14	LT			
98	2122+41 TO 2133+90	RT			
199	TOTAL				

42001200 PAVEMENT FABRIC					REMARKS
SQ YD	LOCATION		OFFSET		
72	2123+83 TO 2124+08				
165	2130+59 TO 2131+16				
237	TOTAL				