

# SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEMS	UNIT	80% FED / 20% STATE TOTAL QUANTITY /007
21400100	GRADING AND SHAPING DITCHES	FOOT	160
28000300	TEMPORARY DITCH CHECKS	EACH	4
28000400	PERIMETER EROSION BARRIER	FOOT	69
28000500	INLET AND PIPE PROTECTION	EACH	3
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	89
48101200	AGGREGATE SHOULDERS, TYPE B	TON	17
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1
51500100	NAME PLATES	EACH	1
54207591	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE-ARCH, EQUIVALENT ROUND-SIZE 36"	FOOT	90
54214941	PRECAST REINFORCED CONCRETE FLARED END SECTIONS-ARCH, EQUIVALENT ROUND-SIZE 36"	EACH	4
63500105	DELINEATORS	EACH	2
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	180
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
XX001135	PAVEMENT PATCHING SPECIAL * SPECIALTY ITEMS	SQ YD	89