

# SCHEDULE OF QUANTITIES

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

UNIT	LOCATION	REMARKS
6	RT 66' 1096 + 5	
8	RT 68' 1096 + 5	
8	LT 30' 1096 + 40	
10	RT 60' 1096 + 20	
6	RT 75' 1096 + 20	
<b>38</b>	<b>TOTAL</b>	

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)

UNIT	LOCATION	REMARKS
15	RT 60' 1096 + 5	
<b>15</b>	<b>TOTAL</b>	

20200100 EARTH EXCAVATION

CU_YD	LOCATION	REMARKS
280	1095 + 0 TO 1096 + 50	
<b>280</b>	<b>TOTAL</b>	

25100630 EROSION CONTROL BLANKET

SQ_YD	LOCATION	REMARKS
47	RT. STA 1095 + 0 TO 1095 + 70	
<b>47</b>	<b>TOTAL</b>	

25100900 TURF REINFORCEMENT MAT

SQ_YD	LOCATION	REMARKS
33.0	RT. STA 1096 + 25 TO 1096 + 80	
26.0	RT. STA 1096 + 25	IN CHANNEL
<b>59.0</b>	<b>TOTAL</b>	

28000300 TEMPORARY DITCH CHECKS

EACH	LOCATION	REMARKS
1	RT. STA 1095 + 50	
1	RT. STA 1096 + 50	
<b>2</b>	<b>TOTAL</b>	

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION	REMARKS
68.0	LT. STA. 1095 + 50 TO 1096 + 10	
75.0	LT. STA. 1096 + 40 TO 1097 + 0	
<b>143.0</b>	<b>TOTAL</b>	

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION	REMARKS
1	RT. STA 1095 + 60	
1	RT. STA 1096 + 35	Culvert AR CULVERT
<b>2</b>	<b>TOTAL</b>	

28100107 STONE RIPRAP, CLASS A4

SQ_YD	LOCATION	REMARKS
24	LT. STA. 1096 + 50	7' X 30'
<b>24</b>	<b>TOTAL</b>	

28200200 FILTER FABRIC

SQ_YD	LOCATION	REMARKS
24	LT. STA. 1096 + 50	
<b>24</b>	<b>TOTAL</b>	

35101400 AGGREGATE BASE COARSE, TYPE B

ION	LOCATION	REMARKS
60	STA. 1096 + 4	LEFT
50	STA. 1095 + 92	RIGHT
27	STA. 1095 + 70 TO 1095 + 32	STAGE 1, 6" THICK, TAPER
	1096 + 42 TO 1097 + 2	STAGE 1, 6" THICK, TAPER
<b>137</b>	<b>TOTAL</b>	

44201383 CLASS C PATCHES, TYPE IV, 12 INCH

SQ_YD	LOCATION	REMARKS
154	1096 + 11 TO 1096 + 64	
<b>154</b>	<b>TOTAL</b>	

48101200 AGGREGATE SHOULDERS TYPE B

ION	LOCATION	REMARKS
20.0	LT 1095 + 70 TO 1097 + 0	
50	RT 1094 + 63 TO 1097 + 0	
<b>70.0</b>	<b>TOTAL</b>	

50100100 REMOVAL OF EXISTING STRUCTURES

EACH	LOCATION	REMARKS
1.0	1096 + 37	
<b>1.0</b>	<b>TOTAL</b>	

54213693 PRECAST REINFORCED CONCRETE FLARED END SECTION 48"

EACH	LOCATION	REMARKS
1.0	LT 1096 + 54	
<b>1.0</b>	<b>TOTAL</b>	

54213450 END SECTIONS 15"

EACH	LOCATION	REMARKS
1.0	RT 1095 + 60	
<b>1.0</b>	<b>TOTAL</b>	