

SCHEDULE OF QUANTITIES

542A0253 PIPE CULVERTS, CLASS A, TYPE I, 48"

FEET	LOCATION	REMARK'S
84.0	1096 + 25RT TO 1096 + 54LT	AR CULVERT ON SKEW
84.0	TOTAL	

542D0220 PIPE CULVERTS, CLASS D, TYPE I, 15"

FEET	LOCATION	REMARK'S
67.0	RT 1095 + 70 TO 1096 + 30	
67.0	TOTAL	

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION	REMARK'S
95	LT. STA. 1096 + 15 TO 1097 + 10	
95	TOTAL	

63500105 DELINEATORS

EACH	LOCATION	REMARK'S
2	LT/RT 1096 + 40	AR Culvert
1	RT 1095 + 55	FE Culvert
3	TOTAL	

66600105 FURNISHING AND ERECTING RIGHT OF WAY MARKERS

EACH	LOCATION	REMARK'S
1	LT 1095 + 33	33' LEFT
1	LT 1095 + 50	50' LEFT
1	LT 1096 + 25	85' LEFT
1	LT 1096 + 65	85' LEFT
1	LT 1097 + 33	33' LEFT
1	RT 1093 + 94	38' RIGHT
1	RT 1095 + 50	55' RIGHT
1	RT 1096 + 10	80' RIGHT
1	RT 1096 + 50	80' RIGHT
1	RT 1097 + 0	42.75 RIGHT
10	TOTAL	

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION	REMARK'S
1		TO BE DETERMINED IN FIELD BY ENGINEER
1	TOTAL	

78001110 PAINT PAVEMENT MARKING - LINE 4"

FOOT	LOCATION	REMARK'S
948	LT/RT 1094 + 63 TO 1097 + 0	WHITE EDGE LINES (TWO COATS)
119	1094 + 63 TO 1097 + 0	YELLOW SKIP DASH (TWO COATS)
1067	TOTAL	

X0323660 DROP BOX NO. 1

EACH	LOCATION	REMARK'S
1	RT 42' 1096 + 25	
1	TOTAL	

X0712400 TEMPORARY PAVEMENT

SQ_YD	LOCATION	REMARK'S
14	RT 1096 + 32 TO 1096 + 42	STAGE I
14	TOTAL	

XX001135 PAVEMENT PATCHING SPECIAL

SQ_YD	LOCATION	REMARK'S
154	1096 + 11 TO 1096 + 64	
154	TOTAL	

Z0005400 BREAKER RUN CRUSHED STONE

TON	LOCATION	REMARK'S
30	1096 + 37	12" THICK X 5' WIDE UNDER PIPE
30	TOTAL	