

GENERAL NOTES

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO ROUTINE VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF THE WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY FURNISHED BASED UPON THE UNIT BID FOR THE WORK.

FOR STABILIZATION, ALL TYPE III BARRICADES SHALL REQUIRE A MINIMUM OF FOUR SAND BAGS PER BARRICADE.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE "JULIE" NUMBER IS 1-800-892-0123. A MINIMUM OF FORTY-EIGHT (48) HOURS ADVANCE NOTICE IS REQUIRED.

WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL MONUMENTS UNTIL AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR HAVING AN AUTHORIZED SURVEYOR REESTABLISH ANY SECTION OR SUBSECTION MONUMENTS DESTROYED BY HIS OPERATIONS.

ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER LISTED ON THE INDEX OF SHEETS OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS.

THE CONTRACTOR SHALL BE REQUIRED TO SECURE WASTE CONTAINERS THAT REMAIN ON THE JOB SITE. THIS WILL ENTAIL THAT ALL WASTE CONTAINERS CAN NOT BE MOVED OR OPENED DURING NON-WORKING HOURS.

WORKING DAYS SHALL BE CHARGED UNTIL THE CONTRACTOR/ SUBCONTRACTOR LICENSED TO DISPOSE OF LEAD PAINT RESIDUE HAS REMOVED THE WASTE MATERIAL FROM THE JOB SITE ACCORDING TO ALL FEDERAL, STATE AND LOCAL LAWS AND ORDINANCES.

THE PAINTING CONTRACTOR SHALL POSSESS CURRENT SSPC-QP1 AND SSPC-QP2 CERTIFICATIONS AT THE TIME OF THE BID, AND SHALL MAINTAIN CERTIFIED STATUS THROUGHOUT THE DURATION OF THE PAINTING WORK UNDER THE CONTRACT.

THE CONTRACTOR SHALL PROVIDE A MINIMUM OF FOUR (4") AMBIENT AIR MONITORS FOR THIS PROJECT THAT SHALL BE USED ACCORDING TO THE SPECIAL PROVISION. FOR "CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES", AND AS DIRECTED BY THE ENGINEER.



THE PIN AND LINK ASSEMBLIES, INCLUDING BUSHINGS AND LUBRICATION PORTS, SHALL BE PROTECTED FROM DAMAGE AND DEBRIS ACCUMULATION DURING CLEANING AND PAINTING OPERATIONS. THE CONTRACTOR SHALL SUBMIT A PROTECTION PLAN FOR REVIEW AND APPROVAL PRIOR TO STARTING THE WORK AROUND THE PIN AND LINKS.

DATE: 10-15-08

PREPARED BY: *Ruth Powell*
DISTRICT STUDIES & PLANS ENGINEER

EXAMINED BY: *Herb Jones*
DISTRICT CONSTRUCTION ENGINEER

My [Signature]
DISTRICT MATERIALS ENGINEER

Bruce A. Heuck
DISTRICT OPERATIONS ENGINEER

△ REVISED 12/31/08

FILE NAME =	USER NAME = woodshankr1	DESIGNED = RON WOODSHANK	REVISED =	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca:\pw\work\PIWIDOT\WOODSHANKR1\dms29378	d366854-ahh-detailed.dgn	DRAWN = RON WOODSHANK	REVISED =			46	(1-BD)BP	LASALLE	38	2	
	PLOT SCALE = 100.0000' / IN.	CHECKED =	REVISED =			CONTRACT NO. 66854					
	PLOT DATE = Oct 15, 2008 - 07:04:42 AM	DATE =	REVISED =			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					