

SUMMARY OF QUANTITIES			
CODE NO.	CONSTRUCTION CODE TYPE:		80% FED. 20% STATE Y007
	ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	245
20400800	FURNISHED EXCAVATION	CU YD	304
20700220	POROUS GRANULAR EMBANKMENT	CU YD	142
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	48
25000200	SEEDING, CLASS 2	ACRE	0.3
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27
25100115	MULCH, METHOD 2	ACRE	0.3
25100630	EROSION CONTROL BLANKET	SQ YD	17
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	30
28000300	TEMPORARY DITCH CHECKS	EACH	4
28000400	PERIMETER EROSION BARRIER	FOOT	200
28000500	INLET AND PIPE PROTECTION	EACH	3
28200200	FILTER FABRIC	SQ YD	100
28100107	STONE RIPRAP, CLASS A4	SQ YD	100
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	225
35501326	HOT-MIX ASPHALT BASE COURSE, 10 1/2"	SQ YD	208
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	319
40600300	AGGREGATE (PRIME COAT)	TON	8
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	0.4
40600525	LEVELING BINDER (HAND METHOD), N50	TON	0.6
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	143
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	346
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	119
44000100	PAVEMENT REMOVAL	SQ YD	208
48101200	AGGREGATE SHOULDERS, TYPE B	TON	10
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	579
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50105200	REMOVE EXISTING CULVERTS	EACH	1
50200100	STRUCTURE EXCAVATION	CU YD	103
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	9535
54002020	EXPANSION BOLTS 3/4 INCH	EACH	52
54003000	CONCRETE BOX CULVERTS	CU YD	35.8
54021005	PRECAST CONCRETE BOX CULVERT 10' X 5' (M273)	FOOT	37

SUMMARY OF QUANTITIES (CONTINUED)			
CODE NO.	CONSTRUCTION CODE TYPE:		80% FED. 20% STATE Y007
	ITEM	UNIT	TOTAL QUANTITY
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	71
54213450	END SECTIONS 15"	EACH	2
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	250
63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	50
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	611
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	980
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	123
78200410	GUARDRAIL MARKERS, TYPE A	EACH	8
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
X0322121	SHEET WATERPROOFING MEMBRANE SYSTEM	SQ YD	125
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1

• SPECIALTY ITEMS