

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE:

SFTY-2A

CODE NO.	ITEM	UNIT	RURAL 100% STATE TOTAL QUANTITY
20300100	CHANNEL EXCAVATION	CU YD	50
20400800	FURNISHED EXCAVATION	CU YD	148.6
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	86
X0326244	PAVED DITCH REMOVAL AND REPLACEMENT	SQ YD	58
48101200	AGGREGATE SHOULDERS, TYPE B	TON	10
50102400	CONCRETE REMOVAL	CU YD	10.6
50200100	STRUCTURE EXCAVATION	CU YD	148.6
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1600
54003000	CONCRETE BOX CULVERTS	CU YD	10.6
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
X0322121	SHEET WATERPROOFING MEMBRANE SYSTEM	SQ YD	90
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1407
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH LESS THEN OR EQUAL TO 5 INCHES)	SQ FT	31