

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE 80% FED 20% STATE	
CODE NO.	ITEM	UNIT	T. QUANTITY	I 000
20100500	TREE REMOVAL, ACRES	ACRE	0.28	0.28
20200100	EARTH EXCAVATION	CU YD	256	256
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	42	42
20400800	FURNISHED EXCAVATION	CU YD	415	415
20700220	POROUS GRANULAR EMBANKMENT	CU YD	4	4
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	22	22
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	796	796
* 25000300	SEEDING, CLASS 3	ACRE	0.25	0.25
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23	23
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23	23
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23	23
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	796	796
28000300	TEMPORARY DITCH CHECKS	EACH	8	8
28000400	PERIMETER EROSION BARRIER	FOOT	60	60
28100207	STONE RIPRAP, CLASS A4	TON	6.5	6.5
28200200	FILTER FABRIC	SQ YD	8.5	8.5

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE 80% FED 20% STATE	
CODE NO.	ITEM	UNIT	T. QUANTITY	I 000
28500100	FABRIC FORMED CONCRETE REVETMENT MAT	SQ YD	441	441
35800100	PREPARATION OF BASE	SQ YD	44	44
35800200	AGGREGATE BASE REPAIR	TON	20	20
40600215	POLYMERIZED BITUMINOUS MATERIAL (PRIME COAT)	TON	91	91
40600300	AGGREGATE (PRIME COAT)	TON	549	549
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX SURFACE REMOVAL - BUTT JOINT	SQ YD	2,052	2,052
40600990	TEMPORARY RAMP	SQ YD	422	422
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	13234	13234
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	291	291
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	158, 157	158,157
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	6471	6471
44000300	CURB REMOVAL	FOOT	215	215
44004250	PAVED SHOULDER REMOVAL	SQ YD	130	130
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	957	957
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	69	69

* SPECIALTY
ITEM