

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE 80% FED 20% STATE	
CODE NO.		UNIT	T. QUANTITY	I 000
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	144	144
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,755	2,755
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	120	120
48203100	HOT-MIX ASPHALT SHOULDERS	TON	3,052	3,052
50102400	CONCRETE REMOVAL	CU YD	1.4	1.4
50800105	REINFORCEMENT BARS	POUND	1,508	1,508
54002020	EXPANSION BOLTS 3/4 INCH	EACH	12	12
54003000	CONCRETE BOX CULVERTS	CU YD	10	10
54215547	METAL END SECTIONS 12"	EACH	2	2
54248510	CONCRETE COLLAR	CU YD	0.5	0.5
60100945	PIPE DRAINS 12"	FOOT	60	60
60900230	TYPE C INLET BOX, STANDARD 609001 (SPECIAL)	EACH	2	2
60900515	CONCRETE THRUST BLOCKS	EACH	2	2
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	462.5	462.5
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3
63200310	GUARDRAIL REMOVAL	FOOT	262.5	262.5

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE 80% FED 20% STATE	
CODE NO.	ITEM	UNIT	T. QUANTITY	I 000
63304385	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1	EACH	5	5
<del>Z0020800</del>	EROSION CONTROL CURB	FOOT	215	215
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	44	44
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	16,298	16,298
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	154,835	154,835
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	495	495
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	320	320
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	20	20
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5,433	5,433
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	154,835	154,835
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	495	495

\* SPECIALTY  
ITEM

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. 317	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			US24	(137.102)RS-4; 10IRS-3	FULTON	4	4	
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -			<b>CONTRACT NO. 68337</b>					
	PLOT DATE = #DATE#	DATE -	REVISED -			SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____	FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT		