

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80/20 1000	80/20 SN 062-0001 X020-2A	80/20 SN 062-0002 X071-2A
20200100	EARTH EXCAVATION	CU YD	1140	1140		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	92	92		
20300100	CHANNEL EXCAVATION	CU YD	965		600	365
20400800	FURNISHED EXCAVATION	CU YD	170	170		
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	145		48	97
21101615	TOPSOIL FURNISH AND PLACE 4"	SO YD	5775	5775		
25000210	SEEDING, CLASS 2A	ACRE	1.4	1.4		
25000350	SEEDING, CLASS 7	ACRE	0.4	0.4		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	131	131		
25000500	PHOSPORUS FERTILIZER NUTRIENT	POUND	131	131		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	131	131		
25100115	MULCH, METHOD 2	ACRE	1.8	1.8		
25100630	EROSION CONTROL BLANKET	SO YD	5618	5618		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	192	192		
28000300	TEMPORARY DITCH CHECKS	EACH	14	14		
28000400	PERIMETER EROSION BARRIER	FOOT	4274	4274		
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	1243		423	820
28200200	FILTER FABRIC	SO YD	1551		660	891
35100100	AGGREGATE BASE COURSE, TYPE A	TON	6	6		
35600720	HOT-MIX ASPHALT BASE COURSE WIDENING, 11"	SO YD	254	254		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.2	1.2		
40600300	AGGREGATE (PRIME COAT)	TON	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	951	951		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N50	TON	1674	1674		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N50	TON	466	466		
42001165	BRIDGE APPROACH PAVEMENT	SO YD	446		224	222
42001300	PROTECTIVE COAT	SO YD	228	228		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	86		46	40
44000100	PAVEMENT REMOVAL	SO YD	669	669		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	49	49		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	685	685		
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1			1
50200100	STRUCTURE EXCAVATION	CU YD	473		132	341

FILE NAME = c:\projects\1251sandy\summaster.dgn	USER NAME = mausherdca	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 251 SANDY CREEK MASTER SUMMARY OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -			253	68(BR, BR-1)	MARSHALL	97	4	
		CHECKED -	REVISED -			CONTRACT NO. 68573					
		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	