SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				80/20 I000	80/20 SN 062-0001 X020-2A	80/20 SN 062-0002 X071-2A
50300100	FLOOR DRAINS	EACH	14		6	8
50300225	CONCRETE STRUCTURES	CU YD	123.5		93.1	30.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	257.7		145.9	111.8
50300260	BRIDGE DECK GROOVING	SQ YD	506		249	257
50300280	CONCRETE ENCASEMENT	CU YD	11.2		6.4	4.8
50300300	PROTECTIVE COAT	SQ YD	667		328	339
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1
50500505	STUD SHEAR CONNECTORS	EACH	1026			1026
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	63130		37550	25580
50800515	BAR SPLICERS	EACH	64			64
51201400	FURNISH STEEL PILES HP10X42	FOOT	436		436	
51201600	FURNISH STEEL PILES HP12X53	FOOT	336			336
51202305	DRIVING PILES	FOOT	772		436	336
51203400	TEST PILE STEEL HP10X42	EACH	2		2	
51203600	TEST PILE STEEL HP12X53	EACH	2			2
51204650	PILE SHOES	EACH	14			14
51500100	NAME PLATES	EACH	2		1	1
52100520	ANCHOR BOLTS, 1"	EACH	24			24
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	104		38	66
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	254		120	134
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	1412	1412		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8	8		
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) FLARED	EACH	8	8		
63200310	GUARDRAIL REMOVAL	FOOT	2243	2243		
66502400	WOVEN WIRE FENCE TO BE REMOVED AND RE-ERECTED	FOOT	1374	1374		
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	2		1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7		
67100100	MOBILIZATION	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30		15	15
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	280	280		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	120	120		
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	2		2	
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	3083	3083		

*SPECIALTY ITEM