

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80/20 1000	80/20 X020-2A	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80/20 1000	80/20 X020-2A
20200100	EARTH EXCAVATION	CU YD	70	70		50300300	PROTECTIVE COAT	SQ YD	328		328
20300100	CHANNEL EXCAVATION	CU YD	600		600	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	37550		37550
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	48		48	51201400	FURNISHING STEEL PILES, HP10X42	FOOT	436		436
21101615	TOPSOIL FURNISH AND PLACE 4"	SO YD	694	694		51202305	DRIVING PILES	FOOT	436		436
25000210	SEEDING, CLASS 2A	ACRE	0.4	0.4		51203400	TEST PILE STEEL HP10X42	EACH	2		2
25000350	SEEDING, CLASS 7	ACRE	0.4	0.4		51500100	NAME PLATES	EACH	1		1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	36	36		59100100	GEOCOMPOSITE WALL DRAIN	SO YD	38		38
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	36	36		60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	120		120
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	36	36		63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	388	388	
25100115	MULCH, METHOD 2	ACRE	0.8	0.8		63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
25100630	EROSION CONTROL BLANKET	SO YD	216	216		63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPL (FLARED)	EACH	4	4	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	80	80		63200310	GUARDRAIL REMOVAL	FOOT	914	914	
28000300	TEMPORARY DITCH CHECKS	EACH	5	5		66502400	WOVEN WIRE FENCE TO BE REMOVED AND RE-ERECTED	FOOT	470	470	
28000400	PERIMETER EROSION BARRIER	FOOT	700	700		66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1		1
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	423		423	67000400	ENGINEERS FIELD OFFICE, TYPE A	CAL MO	3.5	3.5	
28200200	FILTER FABRIC	SO YD	660		660	67100100	MOBILIZATION	L SUM	0.5	0.5	
35100100	AGGREGATE BASE COURSE, TYPE A	TON	6	6		70100500	TRAFFIC CONTROL AND PROTECTION, STD 701326	L SUM	0.5	0.5	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.0	1.0		70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	15		15
40600982	HOT MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	434	434		70300100	SHORT TERM PAVEMENT MARKING	FOOT	120	120	
40603080	HOT MIX ASPHALT BINDER COURSE IL 19.0, N50	TON	220	220		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	40	40	
40603335	HOT MIX ASPHALT SURFACE COURSE, MIX D, N50	TON	233	233		72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	2		2
42001165	BRIDGE APPROACH PAVEMENT	SO YD	224		224	78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1260	1260	
42001300	PROTECTIVE COAT	SO YD	228	228		78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	150	150	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SO YD	46	46		78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6	6	
44000100	PAVEMENT REMOVAL	SO YD	369	369		78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	1		1
48101200	AGGREGATE SHOULDERS, TYPE B	TON	40	40		78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	
48203029	HOT MIX ASPHALT SHOULDERS, 8"	SO YD	685	685		78200520	BARRIER WALL MARKERS, TYPE B	EACH	4		4
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
50200100	STRUCTURE EXCAVATION	CU YD	132		132	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	7	7	
50300100	FLOOR DRAINS	EACH	6		6	X5020501	UNDERWATER STR EXCAVATION PROTECTION - LOC 1	EACH	1		1
50300225	CONCRETE STRUCTURES	CU YD	93.1		93.1	X5020502	UNDERWATER STR EXCAVATION PROTECTION - LOC 2	EACH	1		1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	145.9		145.9	X7011005	TRAFFIC CONTROL AND PROTEC FOR TEMP DETOUR	L SUM	0.5	0.5	
50300260	BRIDGE DECK GROOVING	SO YD	249		249	X7015005	CHANGEABLE MESSAGE SIGN	CAL DAY	14	14	
50300280	CONCRETE ENCASEMENT	CU. YD.	6.4		6.4	Z0013798	CONSTRUCTION LAYOUT	L SUM	0.5	0.5	
						Z0076600	TRAINEES	HOUR	250		250

FOR INFORMATIONAL PURPOSES ONLY

FILE NAME =	USER NAME = meushardce	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES - SN 062-0001	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\projeots\1251sandy\0622001summq.dgn	DRAWN -	REVISED -	253			68(BR, BR-1)	MARSHALL	97	34	
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 68573							
PLOT DATE = 9/18/2008	DATE -	REVISED -	SCALE:			SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT			