

SUMMARY OF QUANTITIES

100% STATE SAFETY-2A McDONOUGH COUNTY				
CODE NO.	ITEM	UNIT	RURAL	TOTAL

100% STATE SFTY-2A McDONOUGH COUNTY				
CODE NO.	ITEM	UNIT	RURAL	TOTAL
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQYD	804	804
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQYD	804	804
50102400	CONCRETE REMOVAL	CUYD	1.3	1.3
50300300	PROTECTIVE COAT	SQ YD	117	117
50400205	PRECAST PRESTRESSED CONCRETE DECK BEAMS (11" DEPTH)	SQFT	587	587
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQFT	379	379
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1210	1210
50900905	REMOVING ^{AND} RE-ERECTING EXISTING RAILING	FOOT	69	69
67100100	MOBILIZATION	LSUM	1	1
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2943	2943
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQFT	982	982
70400100	TEMPORARY CONCRETE BARRIER	FOOT	325	325
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	262.5	262.5
*78005110	EPOXY PAVEMENT MARKING-LINE 4"	FOOT	826	826
78300105	PAVEMENT MARKING REMOVAL	FOOT	826	826
X0320047	REMOVAL OF EXISTING ^{PRECAST PRESTRESSED CONCRETE} DECK BEAMS	SQFT	972	972
X0321781	MECHANICAL SPLICE	EACH	102	102
X5030305	CONCRETE WEARING SURFACE, 5"	SQYD	117	117
*X7200201	WIDTH RESTRICTION SIGNING	LSUM	1	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY(NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1
Z0030350	IMPACT ATTENUATORS, RELOCATE(NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1

* SPECIALTY ITEMS

SN.055-0027 US.67SB
over Farmers Fork