
STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION Remove, Store, & Re-erect exisitng railing 28'-6" New Concrete Wearing Surface Stage II Construction 8'-0" Stage I Construction (For Overlay Only) (For Overlay Only) Limits of Grouted Key (Typ.) Existing Conc. Removal Mechanical Splicer Reinf. Beam 3 Beam 4 Beam 5 Beam 2 Beam 6 Ream 8 Fabric Brg. Stage II Removal & Construction Stage I Removal & Construction Pad (Typ.)

CROSS SECTION - SPAN 1


(Looking South)

* Reinforcement shall extend 6" past edge of concrete to allow installation




CROSS SECTION - SPAN 2

(Looking South)




SHEAR KEY CLAMPING DEVICE

See Special Provisions for Stage Construction Precast Prestressed Concrete Deck Beams. See sheet 1 of 7 for Stage traffic lanes. Cost is included with Precast Prestressed Concrete Deck Beams.



SECTION THRU ABUTMENT



TYPICAL SECTION THRU PIERS

Looking East thru Pier 1 Looking West thru Pier 2

- ** 1" Joint shall be filled with non-shrink grout. Dimension may vary to accommodate tolerance in beam lengths.
- *** Existing dowel rods are to be burned off, ground flush, and sealed with epoxy prior to placement of new beams. Cost included in Removal of Existing PPC Deck Beams. After beams have been erected holes shall be drilled into cap and dowel rods placed. Dowel holes shall be filled with non-shrink grout to top of beam and allowed to cure a minimum of 24 hours prior to grouting the shear keys.

REPAIR DETAILS US ROUTE 67 OVER FARMER'S FORK SN 055-0027

SHEET NO.6	F.A.P. RTE.	SECTION			COUNTY	TOTAL SHEETS	SHEET NO.
	310	-			McDONOUGH	16	15
7 SHEETS					CONTRACT NO.		
	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT						

Kyle M. Steffen ATH

DESIGNED

CHECKED

ATH

EXAMINED