## **SCHEDULE OF QUANTITIES**

		LOCATION OF WORK: VA	RIOUS ROUTES	IL 9	US 136	I-55	US 136	US 24	
		D5 CRACK AND JOINT SE	AL 2009-1	FAP 693	FAP 315 MCLEAN CO.	F.A.I. 55	FAP 315	FAP 317 MCLEAN CO.	
		MCLEAN COUNTY		MCLEAN CO.		MCLEAN CO.	MCLEAN CO.		
				2-LANE RURAL	2-LANE RURAL	<b>4-LANE RURAL</b>	2-LANE RURAL	2-LANE RURAL	
				100% STATE	100% STATE	100% STATE	100% STATE	100% STATE	
				ROUT & SEAL	<b>ROUT &amp; SEAL</b>	<b>ROUT &amp; SEAL</b>	<b>ROUT &amp; SEAL</b>	<b>ROUT &amp; SEAL</b>	
				LOCATION #1	LOCATION #2	LOCATION #3	LOCATION #4	LOCATION #5	
CODE NO.	ITEM	<u>UNIT</u>	TOTAL QUANTITY						
45100100	CRACK ROUTING (PAVEMENT)	FOOT	407,786.0	59,336.0	95,039.0	116,882.0	59,518.0	77,011.0	
45100200	CRACK FILLING	POUND	163,116.0	23,735.0	38,016.0	46,753.0	23,808.0	30,804.0	
67100100	MOBLIZATION	L SUM	1.0	0.1	0.2	0.2	0.1	0.2	
70100460	TRAFFIC CONTROL & PROT. 701306	L SUM	1.0	0.2	0.4	0.0	0.2	0.2	
70100700	TRAFFIC CONTROL & PROT. 701406	L SUM	1.0	0.0	0.0	0.5	0.0	0.0	
78001110	PAINT PAVE.MRK4"	FOOT	29,491.0	7,460.0	7,440.0	0.0	8,955.0	5,636.0	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DAY	28.0	0.0	0.0	28.0	0.0	0.0	

FILE NAME =	USER NAME = austinrl	DESIGNED -	REVISED -		SCHEDULE OF QUANTITIES			SECTION	COUNTY	TOTAL SHEF	,Ŧ
c:\projects\d570736\cadsheets\d570736-s	nt-schedule.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS				D5 CRACK & JOINT SEAL 2009-1	MCLEAN	21 10	$\exists$
	PLOT SCALE = 43.4288 ' / IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION					CONTRACT	T NO. 70736	٦
	PLOT DATE = 10/14/2008	DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS STA. TO STA.	FED. R	OAD DIST NO THINNIS FED A	ID PROJECT		$\dashv$