

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODES	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FAI 72 ROADWAY 4 LANE 90% FED 10% STATE 1000
20200100	EARTH EXCAVATION	CU YD	1268	1268
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.81	0.81
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	81	81
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SO YD	4322	4322
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	19053	19053
40600300	AGGREGATE (PRIME COAT)	TON	380	380
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	44	44
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	71	71
40600990	TEMPORARY RAMP	SO YD	800	800
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N105	TON	13890	13890
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	9541	9541
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SO YD	68415	68415
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	960	960
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SO YD	111145	111145
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	4078	4078
44004250	PAVED SHOULDER REMOVAL	SO YD	3448	3448
44200525	CLASS A PATCHES, TYPE I, 8 INCH	SO YD	518	518
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SO YD	904	904
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SO YD	189	189
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SO YD	400	400
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SO YD	2413	2413
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SO YD	41	41
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SO YD	18	18
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	85	85
44213000	PATCHING REINFORCEMENT	SO YD	3644	3644
44213100	PAVEMENT FABRIC	SO YD	18	18
44213200	SAW CUTS	FOOT	10595	10595
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1352	1352

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODES	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FAI 72 ROADWAY 4 LANE 90% FED 10% STATE 1000
48203043	HOT-MIX ASPHALT SHOULDERS, 11 1/2"	SO YD	3507	3507
48203100	HOT-MIX ASPHALT SHOULDERS	TON	5992	5992
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3	3
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	42	42
60500310	FILLING INLETS, SPECIAL	EACH	8	8
63500105	DELINEATORS	EACH	175	175
64200105	SHOULDER RUMBLE STRIP	FOOT	75717	75717
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	1	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	29208	29208
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1305	1305
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1305	1305
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	81483	81483
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	10246	10246
* 78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	1687	1687
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1078	1078
⊙ X0320157	CLEANING UNDERDRAIN OUTLETS	EACH	122	122
X0322729	MATERIAL TRANSFER DEVICE	TON	22146	22146
X0323644	PAVEMENT MARKING GROOVING	FOOT	128.5	128.5
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	3	3
X4401705	PARTIAL DEPTH REMOVAL	SO YD	848	848
X4421000	PARTIAL DEPTH PATCHING	TON	143	143
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28	28
Z0017100	DOWEL BARS	EACH	120	120
⚠ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0075300	TIE BARS	EACH	197	197
⚠ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2

⊙ NON-PARTICIPATING
* Specialty Items

Rev. 12-18-08

Rev.