

PAVING SCHEDULE
(RAMPS)

PAVING SCHEDULE (RAMPS)						BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	POLYMERIZED HOT MIX ASPHALT SURFACE COURSE, MIX "D", NI05	POLYMERIZED HOT MIX ASPHALT BINDER COURSE, IL-19, 0, NI05	HOT MIX ASPHALT SHOULDERS	HOT MIX ASPHALT SHOULDERS, 1 1/2"	HOT MIX ASPHALT REMOVAL, 1"	HOT MIX ASPHALT REMOVAL, 1 1/2"	HOT MIX ASPHALT REMOVAL, 3 1/4"	HOT MIX ASPHALT REMOVAL, VARIABLE DEPTH	TEMPORARY RAMP	AGGREGATE SHOULDERS, TYPE B
STATION	TO	STATION	LENGTH FEET	RAMP WIDTH FEET	AREA SQ YD	GALLON	TON	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	
RAMP D																	
132+08.20	TO	140+38.58	830.4	16.0	3530.7	203.0	4.1	69.8	104.6	46.5		553.6		738.1		7.9	
126+13.69	TO	132+08.20	594.5	16.0	28111.2	158.5	3.2	88.8	133.2	44.4		528.5		1056.9		68.9	
124+93.80	TO	126+13.69	119.9	16.0	5394.7	34.6	0.7	17.9	26.9	11.2		133.2		213.1		11.2	
RAMP A																	
100+00.00	TO	103+22.00	322.0	16.0	1367.7	78.7	1.6	27.0	40.6	18.0		214.7		286.2		3.1	
103+22.00	TO	106+19.79	297.8	16.0	12381.6	79.4	1.6	44.5	66.7	22.2		264.7		529.4		30.3	
106+19.79	TO	107+62.40	142.6	16.0	3707.9	41.2	0.8	21.3	31.9	13.3		158.5		253.5		7.7	
RAMP C																	
106+26.18	TO	107+05.10	78.9	16.0	2231.1	22.8	0.5	11.8	17.7	7.4		87.7		140.3		4.6	
103+59.03	TO	106+26.18	267.2	16.0	12368.1	71.2	1.4	39.9	59.8	19.9		237.5		474.9		30.3	
100+00.00	TO	103+59.03	359.0	16.0	1370.4	87.8	1.8	30.2	45.2	20.1		239.4		319.1		3.1	
RAMP B																	
114+64.50	TO	115+44.60	80.1	16.0	2082.6	23.1	0.5	12.0	17.9	7.5		89.0		142.4		4.3	
115+44.60	TO	118+81.72	337.1	16.0	26054.6	89.9	1.8	50.3	75.5	25.2		299.7		374.6		63.8	
118+81.72	TO	129+10.60	1028.9	16.0	4360.8	251.5	5.0	86.4	129.6	57.6		685.9		914.6		9.8	
Median Cross Over Sta. 704+30					207.7	20.8	0.0	17.4			207.7						
Median Cross Over Sta. 708+56					207.7	20.8	0.0	17.4			207.7						
SHEET TOTALS			4,458		103,377	1,183	23	535	750	293	0	3,908	0	5,443	0	245	
PROJECT TOTALS			25,360		214,854	19,053	380	9,541	13,890	5,992	3,507	68,415	960	111,145	4,078	800	