

PAVEMENT MARKING SCHEDULE (RAMPS)				SHORT TERM PAVEMENT MARKING	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 4" (YELLOW)	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 4" (WHITE)	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 8"	PERFORMED PLASTIC PAVEMENT MARKING-LINE6"	RAISED REFLECTIVE PAVEMENT MARKER	PAVEMENT MARKING GROOVING
REST AREA RAMPS										
STATION		STATION	FEET	FT.	FT.	FT.	FT.	FT.	EACH	EACH
RAMP D										
124+83.80		125+63.50	79.7	3.2	79.7					
125+63.50		127+23.50	160.0	6.4			160.0			
124+83.80		140+38.60	1,554.8	62.2		1,554.8				
127+23.50		132+07.90	484.4	19.4				121.1		
RAMP A										
100+00.00		107+72.40	772.4	30.9		772.4			17.0	
103+21.60		106+69.80	348.2	13.9			348.2		10.0	
106+69.80		107+72.40	102.6	4.1	102.6					
RAMP C										
100+00.00		107+15.10	715.1	28.6	40.0	715.1			18.0	
103+58.00		106+75.10	317.1	12.7			317.1		9.0	
106+75.10		107+15.10	40.0	1.6						
RAMP B										
114+54.50		114+94.60	40.1	1.6	40.1					
114+94.60		115+91.80	97.2	3.9			97.2			
114+54.50		129+10.58	1,456.1	58.2		1,456.1				
115+91.80		118+82.00	290.2	11.6				72.6		
SHEET TOTALS=			6,458	258	262	4,498	922	194	54	0
PROJECT TOTALS=			27,360	29,208	40,150	41,333	1,687	10,246	1,078	129

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION CUBIC YARD	EARTH EXCAVATION ADJ. FOR SHRINKAGE CUBIC YARD	EMBANKMENT CUBIC YARD	EARTHWORK BALANCE WASTE(+) OR SHORTAGE (-) CUBIC YARD
STA. 852+80.56 TO 857+00.40	1,268	951	83	+868

SHRINKAGE FACTOR = 25%

FILE NAME =	USER NAME = swartzw	DESIGNED - JLD	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\FWIDOT\SWARTZRW\dms36509\sh	sch.74171.dgn	DRAWN - RWS	REVISED -					72	(58,74)(66,67)RS-1	MACON	38	11
	PLOT SCALE = 20.0000' / 1" IN.	CHECKED - WES	REVISED -		SCALE: NA SHEET NO. 4 OF 7 SHEETS STA. TO STA.			CONTRACT NO. 74171				
	PLOT DATE = 10/9/2008	DATE - 10-07	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							