

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		1000	SFTY-2A
20400800	FURNISHED EXCAVATION	CU YD	20	20	
35650700	BASE COURSE WIDENING	SQ YD	560	560	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	14118	14118	
40600300	AGGREGATE (PRIME COAT)	TON	281	281	
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	5259	5259	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2781	2781	
40600990	TEMPORARY RAMP	SQ YD	561	561	
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	10635	10635	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	768	768	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	124589	124589	
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	944		944
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	928	928	
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	4067	4067	
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	324	324	
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	525	525	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3773	3773	
50102400	CONCRETE REMOVAL	CU YD	26.7		26.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	28.2		28.2
50300260	BRIDGE DECK GROOVING	SQ YD	896		896
50300300	PROTECTIVE COAT	SQ YD	1013		1013
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	3460		3460
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	28		28
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3760		3760
50800515	BAR SPLICERS	EACH	48		48
52000110	PREFORMED JOINT STRIP SEAL	FOOT	178		178
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	28		28
52100520	ANCHOR BOLTS, 1"	EACH	56		56
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	375	375	
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	228	228	
63500205	REMOVING AND REPLACING DELINEATORS	EACH	185	185	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	15	15	

SUMMARY OF QUANTITIES (Cont'd)			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		1000	SFTY-2A
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	3	3
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	1		1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	6	4	2
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	13572	13572	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	85708	85708	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6290	6290	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1336	1336	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1508	1508	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	750		750
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	700		700
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	85708	85708	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	6290	6290	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1336	1336	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	820	820	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	8		8
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	59		59
X4421000	PARTIAL DEPTH PATCHING	TON	218	218	
X4422000	PARTIAL DEPTH REMOVAL (VARIABLE DEPTH)	SQ YD	1950	1950	
XZ191200	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/2"	SQ YD	944		944
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	944		944
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	14		14
Z0030250	IMPACT ATTENUATORS, ^{TEMPORARY} (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2		2

* Specialty Items