

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2505	94-P4008-01-BR	KANE	81	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SPECIAL PROVISIONS	SPECIALITY ITEMS	CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONST. TYPE CODE X971-2A	CONST. TYPE CODE Y031-1F
	S	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	235		235
	S	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	245		245
	S	87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1		1
	S	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	4		4
	S	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2		2
	S	88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1		1
	S	88800100	PEDESTRIAN PUSH-BUTTON	EACH	2		2
	S	89502200	MODIFY EXISTING CONTROLLER	EACH	1		1
	S	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1
	S	89502380	REMOVE EXISTING HANDHOLE	EACH	1		1
		Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
		Z0018800	DRAINAGE SYSTEM	L SUM	1	1	
	△	Z0076600	TRAINEES	HOUR	500	500	
		XX002012	RELOCATE SIGN, SPECIAL	EACH	1	1	
		XX003503	FLARED END SECTION REMOVAL	EACH	3	3	
		XX004056	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	3,233	3,233	
		XX004801	BITUMINOUS BIKE PATH REMOVAL	SQ YD	594	594	
		XX005658	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH SPECIAL	SQ FT	2,093	2,093	
		XX007023	STAINING CONCRETE STRUCTURES	SQ YD	320	320	
		X0323017	TEMPORARY INFORMATIONAL SIGNS	EACH	4	4	
		X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	992	992	
		X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	992	992	
	S	X0325890	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	EACH	1	1	
		X2800100	TEMPORARY DITCH CHECKS, ROLLED EXCELSIOR	EACH	11	11	

△ = Y080

PLOT DATE = 11/14/2008
 FILE NAME = H:\AS\CP\B\K\1168648\Bridg\Design\Qry\06.1168648\02.dgn
 PLOT SCALE = NONE
 REFERENCE = #REF*



Robert H. Anderson & Associates, Inc.
 Consulting Engineers
 License No. 184-005281

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 PEDESTRIAN BRIDGE OVER
 RANDALL ROAD AT SILVER GLEN ROAD
 FAU 2505, SECTION 94-P4008-01-BR
 STRUCTURE NUMBER 045-900
 SUMMARY OF QUANTITIES
 SHEET 2 OF 2

SCALE: VERT. DRAWN BY TC
 HORIZ. NONE
 DATE: OCTOBER 31, 2008 CHECKED BY DLS