

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS, 2ZRS-1	CRAWFORD	378	5
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CODE NO.	ITEMS	UNIT	TOTAL QUANTITY	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% CITY	50% STATE 50% CITY
				F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)
				0+915.000 TO 2+756.900 AND 4+475.071 TO 15+545.000	2+756.900 TO 4+475.071	15+545.000 TO 16+016.000	2+756.900 TO 4+475.071	2+756.900 TO 4+475.071
				CONSTRUCTION CODE TYPE				
		1000-2A RURAL	1000-2A RURAL	1000-2A URBAN	SFTY-1B URBAN	SFTY-1B URBAN		
M4248000	DETECTABLE WARNINGS							
M4400715	HOT-MIX ASPHALT SURFACE REMOVAL, 15MM	SQ M	39.7					
M4400725	HOT-MIX ASPHALT SURFACE REMOVAL, 25MM	SQ M	87,188					
M4400740	HOT-MIX ASPHALT SURFACE REMOVAL, 40MM	SQ M	3,400	77,092		6,684		
M4400950	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ M	212			3,400		
M4402000	PAVEMENT REMOVAL	SQ M	10,941			212		
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	11,736	8,933		2,011		
M4402040	COMBINATION CURB AND GUTTER REMOVAL	SQ M	8,669	5,539		6,197		
M4402050	SIDEWALK REMOVAL	METER	2,496	5,716		2,550	403	
M4405000	PAVED DITCH REMOVAL	SQ M	3,767			2,496		
M4420300	PAVEMENT PATCHING, TYPE I 300MM	METER	996			1,927		
M4422300	PAVEMENT PATCHING, TYPE II 300MM	SQ M	322	996			1,840	
M4812150	AGGREGATE SHOULDERS, TYPE B 150MM	SQ M	241	322				
M4820550	HOT-MIX ASPHALT SHOULDERS, 150MM	SQ M	241	241				
M5010521	REMOVE EXISTING CULVERTS	SQ M	23,183	30,124				
M5010522	PIPE CULVERT REMOVAL	METER	180	22,376		21	1,236	
M5030300	CLASS MS CONCRETE	METER	2,137	100		71	9	
M5030350	CONCRETE STRUCTURES	CU M	12.0	1,954		58	125	
M5050405	FURNISHING AND ERECTING STRUCTURAL STEEL	CU M	4.9	4.9		12.0		
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	260	260				
M5401002	PRECAST CONCRETE BOX CULVERT 600MM x 450MM	KG	880	880				
M5401005	PRECAST CONCRETE BOX CULVERT 600MM x 600MM	METER	15.1	15.1				
M5401010	PRECAST CONCRETE BOX CULVERT 900MM x 600MM	METER	15.6	15.6				
M5401020	PRECAST CONCRETE BOX CULVERT 1.2M x 0.6M	METER	5.7	5.7				
M5401060	PRECAST CONCRETE BOX CULVERT 1.8M x 1.2M	METER	19.8	19.8				
M5402020	PRECAST CONCRETE BOX CULVERT 1.2M x 0.6M (M273)	METER	25.2	25.2				
M5402035	PRECAST CONCRETE BOX CULVERT 1.5M x 0.9M (M273)	METER	30.6	30.6				
M5403220	EXPANSION BOLTS M20	METER	9.0	9.0				
M5421210	PIPE CULVERTS, TYPE 1 RCCP 375MM	EACH	206	206				
M5421215	PIPE CULVERTS, TYPE 1 RCCP 450MM	METER	126.5	110.5				
M5421225	PIPE CULVERTS, TYPE 1 RCCP 600MM	METER	66.0	53.5		16.0		
M5421235	PIPE CULVERTS, TYPE 1 RCCP 750MM	METER	118.5	118.5		12.5		
M5421240	PIPE CULVERTS, TYPE 1 RCCP 900MM	METER	32.5	32.5				
M5421260	PIPE CULVERTS, TYPE 1 RCCP 1500MM	METER	55.5	55.5				
M542C212	REINFORCED CONCRETE PIPE TEE, 300MM PIPE WITH 300MM RISER	METER	17.5	17.5				
M542C216	REINFORCED CONCRETE PIPE TEE, 375MM PIPE WITH 300MM RISER	EACH	1		1			
M542C220	REINFORCED CONCRETE PIPE TEE, 450MM PIPE WITH 300MM RISER	EACH	1	1				
M542C228	REINFORCED CONCRETE PIPE TEE, 600MM PIPE WITH 300MM RISER	EACH	2					
M542C236	REINFORCED CONCRETE PIPE TEE, 750MM PIPE WITH 300MM RISER	EACH	8		2			
M542C244	REINFORCED CONCRETE PIPE TEE, 900MM PIPE WITH 300MM RISER	EACH	5		8			
M542C248	REINFORCED CONCRETE PIPE TEE, 1050MM PIPE WITH 300MM RISER	EACH	7		5			
M542C328	REINFORCED CONCRETE PIPE TEE, 600MM PIPE WITH 375MM RISER	EACH	3		7			
M542C336	REINFORCED CONCRETE PIPE TEE, 750MM PIPE WITH 375MM RISER	EACH	1	1	3			
M542E012	END SECTIONS 300MM	EACH	1	1				
M542E016	END SECTIONS 375MM	EACH	1	1				
M542E020	END SECTIONS 450MM	EACH	104	102				
M542E024	END SECTIONS 525MM	EACH	82	70		2		
M542E028	END SECTIONS 600MM	EACH	14	14		12		
M542E032	END SECTIONS 675MM	EACH	48	48				
M542E036	END SECTIONS 750MM	EACH	6	6				
M542E044	END SECTIONS 900MM	EACH	12	12				
M542E048	END SECTIONS 1050MM	EACH	14	14				
M542E116	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 375MM	EACH	4	4				
		EACH	12	10			2	

* SEE SPECIAL PROVISIONS

CONTINUED

PLOT DATE = 11/7/2008
FILE NAME = H:\4428\Drawings\0794533\BRT_081.dwg

H. M. & G. NO. 4420

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SUMMARY OF QUANTITIES</p> <p>SCALE _____ DRAWN BY KOJ</p> <p>DATE OCTOBER 28, 2008 CHECKED BY LWJ</p>

Rev. 12-19-08