

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8419	99-00048-01-PV	FAYETTE	98	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 95500				

CODE NO.	ITEM	UNIT	URBAN - FAYETTE COUNTY					
			TOTAL QUANTITY	FEDERAL 80% CITY 20% TEA-21	FEDERAL 80% CITY 20% STU	CITY 100%	STATE 50% CITY 50%	STATE 100%
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	25	25				
20200100	EARTH EXCAVATION	CU. YD.	500	500				
20800250	TRENCH BACKFILL, SPECIAL	CU. YD.	4240			4240		
21101600	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	90. YD.	1182	315		867		
Δ 25000110	SEEDING, CLASS 1A	ACRE	0.3	0.1		0.2		
Δ 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27	9		18		
Δ 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27	9		18		
Δ 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27	9		18		
Δ 25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.6	0.2		0.4		
Δ 25100630	EROSION CONTROL BLANKET	SQ. YD.	1182	315		867		
Δ 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	30	10		20		
28000500	INLET AND PIPE PROTECTION	EACH	20	10		10		
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ. YD.	192			192		
28200200	FILTER FABRIC	SQ. YD.	192			192		
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	5817	306		354	2208	2949
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	100			100		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	13	13				
42000301	PORTLAND CEMENT CONCRETE PAVEMENT, 8" (JOINTED)	SQ. YD.	9639			1008	4127	4504
42001300	PROTECTIVE COAT	SQ. YD.	15272	4108		1480	4631	5053
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ. YD.	375	329		46		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ. FT.	21170	19165		2005		
42400420	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL	SQ. FT.	732	732				
42400800	DETECTABLE WARNINGS	SQ. FT.	559	559				
44000100	PAVEMENT REMOVAL	SQ. YD.	11227			655	3807	6765
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ. YD.	594	594				
44000300	CURB REMOVAL	FOOT	2298	2298				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	897	646		251		
44000600	SIDEWALK REMOVAL	SQ. FT.	26044	22845		3199		
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	405			405		
44201325	CLASS C PATCHES, TYPE I, 8 INCH	SQ. YD.	4			4		
44201329	CLASS C PATCHES, TYPE II, 8 INCH	SQ. YD.	25			25		
44201333	CLASS C PATCHES, TYPE III, 8 INCH	SQ. YD.	95			95		
44201335	CLASS C PATCHES, TYPE IV, 8 INCH	SQ. YD.	687			687		
44201709	CLASS D PATCHES, TYPE III, 5 INCH	SQ. YD.	34			34		
44201711	CLASS D PATCHES, TYPE IV, 5 INCH	SQ. YD.	419			419		
50104600	CONCRETE RETAINING WALL REMOVAL	FOOT	61	61				
Δ 50607900	CLEANING & PAINTING METAL HANDRAIL	FOOT	56	56				
50900605	HANDRAIL REMOVAL	FOOT	76	76				
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1			1		
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1			1		

Δ SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY KOJ
 CHECKED BY LWJ

CADD FILE: H:\812\des\10\003-006sq-4812.dgn
 PLOTTED: 11/3/2008

H.M. & G. NO. 4812