

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8419	99-00048-01-PV	FAYETTE	98	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 95500				

CODE NO.	ITEM	UNIT	URBAN - FAYETTE COUNTY					
			TOTAL QUANTITY	FEDERAL 80% CITY 20% TEA-21	FEDERAL 80% CITY 20% STU	CITY 100%	STATE 50% CITY 50%	STATE 100%
54216180	REINFORCED CONCRETE PIPE TEE, 12" PIPE WITH 12" RISER	EACH	1		1			
54216190	REINFORCED CONCRETE PIPE TEE, 18" PIPE WITH 12" RISER	EACH	7		7			
54216200	REINFORCED CONCRETE PIPE TEE, 24" PIPE WITH 12" RISER	EACH	18		7	11		
54216210	REINFORCED CONCRETE PIPE TEE, 30" PIPE WITH 12" RISER	EACH	3			3		
54216220	REINFORCED CONCRETE PIPE TEE, 36" PIPE WITH 12" RISER	EACH	6			6		
54248515	CONCRETE COLLAR	EACH	2			2		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	504		173	331		
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	356		189	167		
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	47		47			
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	161		161			
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	309		110	199		
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	181		157	24		
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	741		741			
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	413		152	261		
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	411		411			
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	655		655			
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	308		308			
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	134		134			
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	389		221	168		
550A2560	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 24"	FOOT	32		32			
55100200	STORM SEWER REMOVAL 6"	FOOT	104			104		
55100300	STORM SEWER REMOVAL 8"	FOOT	80			80		
55100400	STORM SEWER REMOVAL 10"	FOOT	326			326		
55100500	STORM SEWER REMOVAL 12"	FOOT	597			597		
55100700	STORM SEWER REMOVAL 15"	FOOT	88			88		
55100900	STORM SEWER REMOVAL 18"	FOOT	211			211		
55101200	STORM SEWER REMOVAL 24"	FOOT	399			399		
552B1100	STORM SEWERS JACKED IN PLACE, CLASS B 30"	FOOT	110			110		
552B1300	STORM SEWERS JACKED IN PLACE, CLASS B 36"	FOOT	119			119		
Δ XX007758	ADJUSTING WATER VALVE BOXES	EACH	5			5		
Δ 56106300	ADJUSTING WATER MAIN 6"	FOOT	255			255		
Δ 56300300	ADJUSTING WATER SERVICE LINES	FOOT	315			315		
Δ 56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	5			5		
Δ 56500300	DOMESTIC METER VAULTS TO BE ADJUSTED	EACH	2			2		
Δ 56500600	DOMESTIC WATER SERVICE BOX TO BE ADJUSTED	EACH	43			43		
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU. YD.	200			200		
60101705	PIPE DRAINS 6" (SPECIAL)	FOOT	76	76				
Δ XX007759	ADJUST SANITARY SEWER CLEANOUT	EACH	34			34		
60218400	MANHOLES, TYPE A, 4' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2				
60224600	RESTRICTED DEPTH MANHOLES, 4' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	4		2		
60225400	RESTRICTED DEPTH MANHOLES, 5' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	9	2		7		

Δ SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY KOJ CHECKED BY LWJ

CADD FILE: H:\4812\des\gn\003-005sq-4812.dgn  
PLOTTED: 11/3/2008