

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
653	*	SHELBY	40	8

EARTH WORK SUMMARY

EARTH EXCAVATION = 488 CU YD
 MAINLINE EMBANKMENT = 4972 CU YD
 FE STA 19+10 EMBANKMENT = 69 CU TD
 FE STA 22+54 EMBANKMENT = 188 CUYD
 FURINISHED EXCAVATION FROM EARTH EXCAVATION = 366 CU YD
 FURINISHED EXCAVATION = 4863 CU YD
 * CHANNEL EXCAVATION = 2375 CU YD

* NO SUITABLE MATERIALS SHOULD COME FROM THE CHANNEL EXCAVATION

**SEEDING QUANTITIES
STA 14+50 TO STA 27+00**

ITEM	RATE OF APPLICATION	QUANTITIES
SEEDING CLASS 2	ART 250.07	2.8 ACRES
NITROGEN FERTILIZER NUTRIENTS	90 LBS./ACRE	252 POUND
PHOSPHORUS FERTILIZER NUTRIENTS	90 LBS./ACRE	252 POUND
POTASSIUM FERTILIZER NUTRIENTS	90 LBS./ACRE	252 POUND
MULCH METHOD 2	2 TONS / ACRE	2.8 ACRES

THE SEEDING MIXTURE SHALL CONFORM TO ROADSIDE MIXTURE TYPE 2, DURING THE PERIOD BETWEEN OCTOBER 1ST AND NOVEMBER 1ST THE CONTRACTOR SHALL ADD 48 POUNDS OF OATS, SPRING TO THE MIXTURE.

SHELBY COUNTY HIGHWAY DEPARTMENT
VARIOUS SCHEDULES
SECTION 04-00256-00-BR