

TEMPORARY PAINT PAVEMENT MARKING				
STA TO STA	O/S	LOCATION	COLOR	QUANTITY
300+50 TO 302+25	LT	NORTH EDGE LINE	WHITE	175 FOOT
300+50 TO 302+25	CENTERLINE	DOUBLE, CENTERLINE	YELLOW	350 FOOT
300+50 TO 302+25	RT	SOUTH EDGE LINE	WHITE	175 FOOT
			TOTAL	700 FOOT

PROPOSED GUARDRAIL INSTALLATION					
O/S	STA TO STA	(EACH) TRAFFIC BARRIER TERMINAL TY 1 SPECIAL (TANG)	(EACH) TRAFFIC BARRIER TERMINAL TY 6A	(FOOT) SPBGR TY A	(FOOT) SPBGR TY A (SHORT RADIUS)
LT	19+71.83 TO 20+15.83		1		
LT	19+21.83 TO 19+71.83	1			
RT	19+69.83 TO 20+13.83		1		
RT	19+44.83 TO 19+69.83			25	
RT	18+94.83 TO 19+44.83	1			
LT	21+98.17 TO 22+42.17		1		
LT	22+42.17 TO 22+67.17			25	
LT	22+67.17 TO 23+17.17	1			
RT	21+96.17 TO 22+40.17		1		
RT	22+40.17 TO 22+55.17				25
	TOTAL	3 EACH	4 EACH	50 FOOT	25 FOOT

TERMINAL MARKER - DIRECT APPLIED		
STA	O/S	QUANTITY
19+21.83	15 LT	1.0 EACH
18+94.83	15 RT	1.0 EACH
23+17.17	15 LT	1.0 EACH
22+55.17	30 RT	1.0 EACH
	TOTAL	4.0 EACH

RAISED PAVEMENT MARKERS		
STA TO STA	RAISED PAVEMENT MARKERS	RAISED PAVEMENT MARKERS BRIDGE
14+50.00 TO 20+14.83	15	-
20+14.83 TO 21+97.17	-	4
21+97.17 TO 27+50.00	13	-
TOTALS	28	4 EACH

TEMPORARY MARKINGS & REMOVAL			
STA TO STA	O/S	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
14+50 TO 27+00	CENTERLINE SURFACE MAT	132 FOOT	-
14+50 TO 27+00	CENTERLINE SURFACE MAT	-	44 SQ. FT.
	TOTAL	132 FOOT	44 SQ. FT.

PAINT 4" LINE				
STA TO STA	O/S	LOCATION	COLOR	QUANTITY
14+50 TO 27+00	LT	NORTH EDGE LINE	WHITE	1250 FOOT
14+50 TO 27+00	CENTERLINE	DOUBLE NO PASSING CENTERLINE	YELLOW	2500 FOOT
14+50 TO 27+00	RT	SOUTH EDGE LINE	WHITE	1250 FOOT
	TOTAL			5000 FOOT

SHELBY COUNTY HIGHWAY DEPARTMENT
SAFETY SCHEDULES
SECTION 04-00256-00-BR