

PAVING ITEMS

STATION TO STATION	PROCESSING MODIFIED SOIL 12"	LIME	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	PORTLAND CEMENT CONCRETE PAVEMENT 8 1/2" (JOINTED)	BRIDGE APPROACH PAVEMENT	PROTECTIVE COAT	PORTLAND CEMENT CONCRETE SIDEWALK, 4"	CONCRETE GUTTER, TYPE A	COMBINATION CONCRETE CURB & GUTTER, TYPE B&C
	SQ YD	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ FT	FOOT	FOOT
23+43.56, LT TO 35+09.37, LT							4,738		
24+27.27 RT TO 34+87.15 RT									1,067
24+27.57 X TO 34+83.29 X	4,007	77.2	4,007	3,053					
24+27.57 X TO 36+13.29 X						3,863			
24+27.86 LT TO 34+79.43 LT									1,044
34+83.29 X TO 35+13.29 X					100				
35+39.61 LT TO 35+53.71 LT								38	
35+64.49 RT TO 35+67.20 RT								24	
36+79.63 LT TO 36+81.86 LT								22	
36+92.59 RT TO 37+45.31 RT								114	
37+35.57 LT TO 37+67.09 LT					100		158		
37+40.95 X TO 37+70.95 X						100			
GRAND TOTAL	4,007	77.2	4,007	3,053	200	3,963	4,896	198	2,111

FENCE SCHEDULE

STATION TO STATION	WOVEN WIRE FENCE, 4"	WOVEN WIRE FENCE TO BE REMOVED AND RE-ERECTED
	FOOT	FOOT
LT 33+75.88 TO LT 34+04.10		72
LT 34+04.10 TO RT 34+20.64		
LT 34+04.10 TO LT 35+11.73	116	
RT 34+20.64 TO RT 34+31.99		42
RT 34+80.39 TO RT 35+21.14	49	
LT 37+32.07 TO LT 38+31.05	108	
LT 37+36.16 TO LT 38+31.05		138
RT 37+41.38 TO RT 37+85.76	53	
LT 38+31.05 TO RT 38+44.28		
RT 38+44.28 TO RT 38+60.24		108
LT 44+81.95 TO LT 48+29.33	380	
GRAND TOTAL	706	360

EXP. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00016-03-BR	MADISON	129	5
STA.		TO STA.		
CONTRACT NO.: 97351				
ADDENDUM #1 01-02-2009				

REMOVAL ITEMS

STATION TO STATION	CURB REMOVAL	WOODEN FENCE REMOVAL	REMOVE EXISTING RIPRAP	WOVEN WIRE FENCE REMOVAL
	FOOT	FOOT	SQ YD	FOOT
LT 23+43.56 TO LT 23+43.74	4			
X 24+27.57 TO X 24+43.51			70	
LT 34+04.10 TO RT 34+20.64				60
LT 38+31.05 TO RT 38+44.28				59
LT 44+81.95 TO RT 47+15.99		310		
RT 47+43.06 TO LT 48+29.33		204		
GRAND TOTAL	4	514	70	119

TREE REMOVAL SCHEDULES

STATION TO STATION	TREE REMOVAL, ACRES
X 26+82.87 TO X 34+33.05	1.85
X 38+24.76 TO X 47+01.91	2.79
X 47+47.77 TO X 50+70.00	0.89
GRAND TOTAL	5.53

REVISED 1-6-09