F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00016-03-BR	MADISON	129	121

STA. 43+77 TO STA. 44+00

CONTRACT NO.: 97351

ADDENDUM #1 01-22-2009

FINAL SURVEY	BY	DATE
SURVEYED	D.L.W.	1/18/06
PLOTTED		
TEMPLATE		
NOTE BOOK	AREAS	
NO.	AREAS CHECKED	

ORIGINAL SURVEY	BY	DATE
SURVEYED	D.L.W.	8/28/05
PLOTTED		
TEMPLATE		
NOTE BOOK	AREAS	
NO.	AREAS CHECKED	

44+00: CUT = 1451.23 SF, FILL = 0.00 SF

43+92: CUT = 1310.84 SF, FILL = 0.00 SF

43+82: CUT = 1081.85 SF, FILL = 0.00 SF

43+77: CUT = 945.51 SF, FILL = 0.00 SF

PROPOSED R.O.W.

PROPOSED P.G.L.

3.00:1

479.70 495.7

479.95 494.1

480.25 492.0

480.40 491.0

REVISED 1-6-09

SCALE
HORIZ. 1"=10'
VERT. 1"=5'

CROSS SECTIONS–WEST CORBIN STREET – STA. 43+77 TO STA. 44+00