PAVEMENT MARKING SCHEDULE

LOCATION	TEMPORARY 24" SINGLE WHITE STOP BAR	TEMPORARY 4" SINGLE WHITE EDGE LINE	TEMPORARY 4" SOLID YELLOW CENTERLINE	EPOXY PAVEMENT MARKING PERMANENT 4" SINGLE WHITE EDGE LINE	EPOXY PAVEMENT MARKING PERMANENT 4" SOLID YELLOW CENTERLINE	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	EACH	EACH
FAS 2881 RALEIGH RD										
STAGE I										
LT. STA. 127+70.50 TO LT. STA. 134+61.50								230		
LCL. STA. 127+70.50 TO LCL. STA. 134+61.50								230		10
RCL. STA. 127+70.50 TO RCL. STA. 134+61.50								230		
RT. STA. 127+70.50 TO RT. STA. 134+61.50								230		
LT. STA. 127+70.50 TO LT. STA. 134+61.50	12	691					228			
RT. STA. 127+70.50 TO LT. STA. 129+78.50		208					69			
LT. STA. 129+78.50 TO LT. STA. 132+53.50		275					91			
LT. STA. 132+53.50 TO RT. STA. 134+61.60	12	208					69			
STAGE II										
LT. STA. 127+70.50 TO RT. STA. 129+78.50		208					69			
RT. STA. 129+78.50 TO RT. STA. 133+03.50		325					107			
RT. STA. 133+03.50 TO LT. STA. 134+61.50		158					53			
RT. STA. 127+70.50 TO RT. STA. 134+61.50		691					228			
LT. STA. 127+70.50							24			
RT. STA. 134+61.60							24			
LT. STA. 127+70.50 TO LT. STA. 134+61.50		691		691			228			
LCL. STA. 127+70.50 TO LCL. STA. 134+61.50			691		691	276	274		10	
RCL. STA. 127+70.50 TO RCL. STA. 134+61.50			691		691		228			
RT. STA. 127+70.50 TO RT. STA. 134+61.50		691		691			228			
SUBTOTAL	24	4146	1382	1382	1382	276	1920	920	10	10
TOTAL	24	5528		2764		276	1920	920	10	10

MAINTENANCE OF TRAFFIC

LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	BARRIER WALL MARKERS	TEMPORARY BRIDGE TRAFFIC SIGNALS	TEMPORARY RUMBLE STRIPS	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3
	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH
FAS 2881 RALEIGH RD							
STAGE I							
127+70.5 TO134+61.5				1	6	2	
STA. 128+98.5 TO STA. 133+33.5	375		15				
STAGE II							
127+70.5 TO134+61.5							2
STA. 128+98.5 TO STA. 133+33.5		375					
TOTAL	375	375	15	1	6	2	2