

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE														
				A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
				0003 URBAN	0040 URBAN	0040 URBAN	0040 URBAN	0040 URBAN	0010 URBAN	0010 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0028 URBAN	0028 URBAN	0003 URBAN	0003 URBAN
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1								0.55							0.45
50104400	CONCRETE HEADWALL REMOVAL	EACH	8															8
50157300	PROTECTIVE SHIELD	SQ YD	3970							1150	2820							
50200100	STRUCTURE EXCAVATION	CU YD	2316		123	115	192	177										1709
50300225	CONCRETE STRUCTURES	CU YD	1059.5		24.4	150.0	134.3	105.8	36.0	40.0								569.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1709.0						793.0	916.0								
50300260	BRIDGE DECK GROOVING	SQ YD	3062						1531	1531								
50300280	CONCRETE ENCASEMENT	CU YD	28.0															28.0
50300285	FORM LINER TEXTURED SURFACE	SQ FT	4629			1555	1877	1197										
50300300	PROTECTIVE COAT	SQ YD	4433						2062	2371								
50400745	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 72"	FOOT	4256															4256
50500505	STUD SHEAR CONNECTORS	EACH	2099			650	436	345										668

X SPECIALTY ITEM

- A ROADWAY AND DRAINAGE - 100% STATE
- B RETAINING WALL SN 022-W063 - 100% STATE
- C RETAINING WALL SN 022-W064 - 100% STATE
- D RETAINING WALL SN 022-W065 - 100% STATE
- E RETAINING WALL SN 022-W066 - 100% STATE
- F BRIDGE SN 022-2029 - 100% STATE
- G BRIDGE SN 022-2030 - 100% STATE

- H LIGHTING - 100% STATE
- I TRAFFIC SIGNALS, TRAFFIC SIGNAL INTERCONNECT, TEMPORARY TRAFFIC SIGNAL INTERCONNECT - 100% STATE
- J TRAFFIC SIGNALS EVP EQUIPMENT - 100% NAPERVILLE
- K NEW SIDEWALK - 80% STATE, 20% NAPERVILLE
- L SHARED-USE PATH - 80% STATE, 20% NAPERVILLE

- M SHARED-USE PATH - 100% NAPERVILLE
- N ROADWAY ITEMS - 100% STATE
- O ROADWAY, DRAINAGE, RETAINING WALLS, LIGHTING AND BRIDGE SUBSTRUCTURE - 100% TOLLWAY

Rev. 1-3-13

FILE NAME:	USER NAME: JHSON	DESIGNED: PJO	REVISED:	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILE #:	DRAWN: RES	CHECKED: JCM	REVISED:									338	(112 & 113) WRS-5	DUPAGE	963	11
PILOT SCALE: 1"=500'±	DATE: 10/15/2012	REVISED:	REVISED:	SCALE:	SHEET NO. 6 OF 41 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 60131								