EARTHWORK VOLUME (CU YD)

Station To Station		Length	Earth Excavation (Suitable Cut)					Earth Excavation (15% S.F.) Used for Embankment					Embankment (Suitable Fill)					Earthwork Balance (cu yd) (+) - Wastage / (-) - Shortage					Topsoil Excavation And Placement					Removal & Disposal of Unsuitable Material					Aggregate Subgrade Improvement				
			Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4	Pre - Stage	Stage 1	Stage 2	Stage 3	Stage 4
1026+00	1026+50	50.0	0	81	0	0	0	0	69	0	0	0	0	70	0	0	0	0	-1	0	0	0	0	68	0	0	0	0	0	0	0	0	0	0	0	0	0
1026+50	1027+00	50.0	0	78	0	0	0	0	66	0	0	0	0	83	0	0	0	0	-16	0	0	0	0	72	0	0	0	0	0	0	0	0	0	0	0	0	0
1027+00	1027+50	50.0	0	71	0	0	0	0	61	0	0	0	0	94	0	0	0	0	-33	0	0	0	0	68	0	0	0	0	0	0	0	0	0	0	0	0	0
1027+50	1028+00	50.0	0	74	0	0	0	0	63	0	0	0	0	99	0	0	0	0	-36	0	0	0	0	69	0	0	0	0	0	0	0	0	0	0	0	0	0
1028+00	1028+50	50.0	0	77	0	0	0	0	66	0	0	0	0	100	0	0	0	0	-35	0	0	0	0	75	0	0	0	0	0	0	0	0	0	0	0	0	0
1028+50	1029+00	50.0	0	80	0	0	0	0	68	0	0	0	0	96	0	0	0	0	-28	0	0	0	0	74	0	0	0	0	0	0	0	0	0	0	0	0	0
1029+00	1029+50	50.0	0	86	0	0	0	0	73	0	0	0	0	93	0	0	0	0	-19	0	0	0	0	75	0	0	0	0	0	0	0	0	0	0	0	0	0
1029+50	1030+00	50.0	0	85	0	0	0	0	72	0	0	0	0	98	0	0	0	0	-25	0	0	0	0	81	0	0	0	0	0	0	0	0	0	0	0	0	0
1030+00	1030+50	50.0	0	79	0	0	0	0	67	0	0	0	0	102	0	0	0	0	-35	0	0	0	0	90	0	0	0	0	0	0	0	0	0	0	0	0	0
1030+50	1031+00	50.0	0	75	0	0	0	0	64	0	0	0	0	100	0	0	0	0	-37	0	0	0	0	95	0	0	0	0	0	0	0	0	0	0	0	0	0
1031+00	1031+50	50.0	0	77	0	0	0	0	65	0	0	0	0	96	0	0	0	0	-30	0	0	0	0	89	0	0	0	0	0	0	0	0	0	0	0	0	0
1031+50	1032+00	50.0	0	78	0	0	0	0	66	0	0	0	0	99	0	0	0	0	-32	0	0	0	0	82	0	0	0	0	0	0	0	0	0	0	0	0	0
1032+00	1032+50	50.0	0	78	0	0	0	0	66	0	0	0	0	100	0	0	0	0	-34	0	0	0	0	79	0	0	0	0	0	0	0	0	0	0	0	0	0
1032+50	1033+00	50.0	0	83	0	0	0	0	71	0	0	0	0	96	0	0	0	0	-25	0	0	0	0	81	0	0	0	0	0	0	0	0	0	0	0	0	0
1033+00	1033+50	50.0	0	70	0	0	0	0	60	0	0	0	0	106	0	0	0	0	-36	0	0	0	0	76	0	0	0	0	0	0	0	0	0	0	0	0	0
1033+50	1034+00	50.0	0	52	A	0	0	0	44	A	0	0	0	116	A	0	0	0	-72	A	0	0	0	69	A	0	0	0	0	0	0	0	0	0	0	0	0
1034+00	1034+50	50.0	0	51	A	0	0	0	44	A	0	0	0	123	A	0	0	0	-80	A	0	0	0	72	A	0	0	0	0	0	0	0	0	0	0	0	0
1034+50	1035+00	50.0	0	53	0	0	0	0	45	0	0	0	0	122	0	0	0	0	-77	0	0	0	0	73	0	0	0	0	0	0	0	0	0	0	0	0	0
1035+00	1035+50	50.0	0	56	0	0	0	0	48	0	0	0	0	108	0	0	0	0	-60	0	0	0	0	72	0	0	0	0	0	24	0	0	0	0	24	0	0
1035+50	1036+00	50.0	0	58	0	0	0	0	49	0	0	0	0	80	0	0	0	0	-31	0	0	0	0	63	0	0	0	0	0	25	0	0	0	0	25	0	0
1036+00	1036+50	50.0	0	58	0	0	0	0	49	0	0	0	0	60	0	0	0	0	-10	0	0	0	0	53	0	0	0	0	0	25	0	0	0	0	25	0	0
1036+50	1037+00	50.0	0	64	0	0	0	0	54	0	0	0	0	48	0	0	0	0	7	0	0	0	0	47	0	0	0	0	0	25	0	0	0	0	25	0	0
1037+00	1037+50	50.0	0	71	0	0	0	0	60	0	0	0	0	34	0	0	0	0	26	0	0	0	0	40	0	0	0	0	0	25	0	0	0	0	25	0	0
1037+50	1038+00	50.0	0	75	0	0	0	0	64	0	0	0	0	37	0	0	0	0	27	0	0	0	0	43	0	0	0	0	0	25	0	0	0	0	25	0	0
1038+00	1038+50	50.0	0	74	0	0	0	0	63	0	0	0	0	36	0	0	0	0	26	0	0	0	0	42	0	0	0	0	0	25	0	0	0	0	25	0	0
1038+50	1039+00	50.0	0	72	0	0	0	0	62	0	0	0	0	44	0	0	0	0	17	0	0	0	0	48	0	0	0	0	0	25	0	0	0	0	25	0	0
1039+00	1039+50	50.0	0	69	0	0	0	0	59	0	0	0	0	51	0	0	0	0	7	0	0	0	0	50	0	0	0	0	0	25	0	0	0	0	25	0	0
1039+50	1040+00	50.0	0	62	0	0	0	0	52	0	0	0	0	45	0	0	0	0	7	0	0	0	0	43	0	0	0	0	0	19	0	0	0	0	19	0	0
1040+00	1040+50	50.0	0	56	0	0	0	0	48	0	0	0	0	43	0	0	0	0	5	0	0	0	0	42	0	0	0	0	0	11	0	0	0	0	11	0	0
1040+50	1041+00	50.0	0	53	0	0	0	0	45	0	0	0	0	41	0	0	0	0	4	0	0	0	0	39	0	0	0	0	0	9	0	0	0	0	9	0	0
1041+00	1041+50	50.0	0	44	0	0	0	0	37	0	0	0	0	43	0	0	0	0	-6	0	0	0	0	41	0	0	0	0	0	0	0	0	0	0	0	0	0
1041+50				A					A					A					A					A													
SUB-TOTAL =>>			636	4928	2729	5436	0	540	4189	2319	4620	0	7083	5658	8359	362	0	-6543	-1469	-6039	4258	0	1690	3354	1576	0	0	0	263	0	0	0	0	263	0	0	0
RAMP B (I-88 WB OFF-RAMP)																																					
8959+48	8960+00	52.0	0	46	0	0	0	0	39	0	0	0	0	26	0	0	0	0	13	0	0	0	0	48	0	0	0	0	0	0	0	0	0	0	0	0	0
8960+00	8960+50	50.0	0	71	0	0	0	0	60	0	0	0	0	30	0	0	0	0	30	0	0	0	0	75	0	0	0	0	0	0	0	0	0	0	0	0	0
8960+50	8961+00	50.0	0	85	0	0	0	0	72	0	0	0	0	41	0	0	0	0	31	0	0	0	0	87	0	0	0	0	0	0	0	0	0	0	0	0	0
8961+00	8961+50	50.0	0	73	0	0	0	0	62	0	0	0	0	53	0	0	0	0	10	0	0	0	0	92	0	0	0	0	0	0	0	0	0	0	0	0	0
8961+50	8962+00	50.0	0	70	0	0	0	0	59	0	0	0	0	65	0	0	0	0	-6	0	0	0	0	95	0	0	0	0	0	0	0	0	0	0	0	0	0
8962+00	8962+50	50.0	0	62	0	0	0	0	53	0	0	0	0	78	0	0	0	0	-25	0	0	0	0	85	0	0	0	0	0	0	0	0	0	0	0	0	0
8962+50	8963+00	50.0	0	53	0	0	0	0	45	0	0	0	0	84	0	0	0	0	-39	0	0	0	0	73	0	0	0	0	0	0	0	0	0	0	0	0	0
8963+00	8963+50	50.0	0	54	0	0	0	0	46	0	0	0	0	69	0	0	0	0	-23	0	0	0	0	68	0	0	0	0	0	0	0	0	0	0	0	0	0
8963+50	8964+00	50.0	0	52	0	0	0	0	44	0	0	0	0	55	0	0	0	0	-11	0	0	0	0	67	0	0	0	0	0	0	0	0	0	0	0	0	0
8964+00	8964+50	50.0	0	50	0	0	0	0	42	0	0	0	0	50	0	0	0	0	-8	0	0	0	0	73	0	0	0	0	0	0	0	0	0	0	0	0	0
8964+50	8965+00	50.0	0	52	0	0	0	0	44	0	0	0	0	42	0	0	0	0	2	0	0	0	0	80	0	0	0	0	0	0	0	0	0	0	0	0	0
8965+00	8965+50	50.0	0	60	0	0	0	0	51	0	0	0	0	43	0	0	0	0	8	0	0	0	0	61	0	0	0	0	0	0	0	0	0	0	0	0	0
8965+50	8966+00	50.0	0	66	0	0	0	0	56	0	0	0	0	45	0	0	0	0	12	0	0	0	0	39	0	0	0	0	0	0	0	0	0	0	0	0	0
8966+00	8966+50	50.0	0	65	0	0	0	0	55	0	0	0	0	42	0	0	0	0	14	0	0	0	0	37	0	0	0	0	0	0	0	0	0	0	0	0	0
8966+50	8967+00	50.0	0	67	0	0	0	0	57	0	0	0	0	44	0	0	0	0	13	0	0	0	0	39	0	0	0	0	0	0	0	0	0	0	0	0	0
8967+00	8967+50	50.0	0	69	0	0	0	0	59	0	0	0	0	45	0	0	0	0	14	0	0	0	0	39	0	0	0	0	0	0	0	0	0	0	0	0	0
8967+50																																					
(NO EARTHWORK IN BETWEEN)																																					
				Stage 1A					Stage 1A					Stage 1A					Stage 1A					Stage 1A					Stage 1A					Stage 1A			
8990+50	8991+00	50.0	9	1	0	0	0	8	1	0	0	0	0	0	13	0	0	8	1	-13	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8991+00	8991+50	50.0	22	2	3	0	0	19	2	2	0	0	12	0	20	0	0	7	1	-18	0	0	13	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8991+50	8992+00	50.0	27	1	7	0	0	23	1	6	0	0	28	1	23	0	0	-4	1	-17	0	0	30	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8992+00	8992+50	50.0	32	1	13	0	0	27	1	11	0	0	37	0	23	0	0	-10	1	-11	0	0	40	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8992+50	8993+00	50.0	33	1	23	0	0	28	1	20	0	0	49	1	21	0	0	-22	1	-2	0	0	46	0	0	0	0	0	0	0	0	0	0	0	0	0	0
8993+00	8993+50	50.0	30	1	26	0	0	25	1	22	0	0	57	1	20	0	0	-32	0	2	0	0	48	0	0	0	0	0	0	0	0	0	0	0	0	0	0

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED PJO	REVISED - ADDENDUM A 12/17/2012	**STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION**	**SCHEDULE OF QUANTITIES EARTHWORK ITEMS**	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN KES	REVISED -			338	(112 & 113) WRS-5	DUPAGE	963	67
	PLOT SCALE = #SCALE#	CHECKED JCM	REVISED -						CONTRACT NO. 60I31	
	PLOT DATE = #DATE#	DATE 10/15/2012	REVISED -		SCALE: SHEET NO. 3 OF 12 SHEETS STA. TO STA.			ILLINOIS	FED. AID PROJECT	