

**A**

CONTRACTOR FOR CONTRACT 60131 SHALL BE RESPONSIBLE FOR INSTALLING AND MAINTAINING THE TEMPORARY OVERHEAD PORTION AND BURIED FIBER OPTIC INTERCONNECT BETWEEN DIEHL RD AND I-88 SOUTH RAMP.

IF CONTRACT 60R31 HAS NOT YET BEEN COMPLETED AT THE COMPLETION OF CONTRACT 60131, THE MAINTENANCE RESPONSIBILITY FOR THE TEMPORARY OVERHEAD FIBER OPTIC INTERCONNECT SHALL BE TRANSFERRED TO CONTRACT 60R31.

IF CONTRACT 60R31 HAS NOT STARTED CONSTRUCTION AT THE COMPLETION OF CONTRACT 60131 OR AS OTHERWISE DIRECTED BY THE ENGINEER, THE MAINTENANCE RESPONSIBILITY FOR THE TEMPORARY OVERHEAD FIBER OPTIC INTERCONNECT SHALL BE TRANSFERRED TO IDOT.


**A**

PERMANENT INTERCONNECT TO BE IN PLACE BETWEEN ODI-COMMUNICATIONS CABINET AND FERRY ROAD (SEE PERMANENT INTERCONNECT PLAN).

THE CONTRACTOR SHALL COORDINATE THE INSTALLATION OF THE TEMPORARY AERIAL FIBER OPTIC CABLE WITH THE ENGINEER PRIOR TO BEGINNING THIS WORK. COORDINATION WITH CONTRACT 60R31 OF THIS WORK AT IL ROUTE 59 AND DIEHL ROAD IS REQUIRED.

FOR MOT STAGES 4-4B ALL INTERCONNECT BETWEEN DIEHL ROAD AND FERRY ROAD SHALL NO LONGER BE WIRELESS. FOR EXISTING CONDUIT SIZES AND LENGTHS SEE PROPOSED INTERCONNECT PLAN.

THE TEMPORARY TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.



FILE NAME: 0711CL4	USER NAME: *USER*	DESIGNED: DW	REVISED: -ADDENDUM A 12/17/2012	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>TEMPORARY INTERCONNECT PLAN IL ROUTE 59 FROM DIEHL ROAD TO FERRY ROAD (STAGE 4 TO STAGE 4B)</b>			F.A. RTE. 338	SECTION (112 & 113) WRS-5	COUNTY DUPAGE	TOTAL SHEETS 963	SHEET NO. 460
	PLOT SCALE: *SCALE*	DRAWN: JDH	REVISED: -		SCALE: 1"=50'	SHEET NO. 45 OF 53 SHEETS	STA. TO STA.	<b>TS-44</b>		CONTRACT NO. 60131		
	PLOT DATE: *DATE*	CHECKED: KMM	REVISED: -					ILLINOIS FED. AID PROJECT				
		DATE: 10/15/2012	REVISED: -									