

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				URBAN					
				ROADWAY 0004	80% FED/ 15% STATE/ 5% LEMONT TRAFFIC SIGNALS 0021	90% FED/ 15% STATE/ 5% LEMONT TRAFFIC SIGNAL INTERCONNECT 0024	100% LEMONT SAFETY 0021	400% LEMONT EMERGENCY VEHICLE PREEMPTION (EVP) 0024	400% LEMONT LOCAL 0024
81028230	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3 1/2" DIA.	FOOT	27		27				
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	661		661				
81400100	HANDHOLE	EACH	6		6				
81400200	HEAVY-DUTY HANDHOLE	EACH	6		6				
81400300	DOUBLE HANDHOLE	EACH	2		2				
84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	1				1		
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2				2		
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1				
86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1		1				
86400100	TRANSCEIVER - FIBER OPTIC	EACH	2		2				
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2533		2533				
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	3061		467		2594		
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1457		1457				
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1481		1481				
87301295	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 20 3C	FOOT	467		467				
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1745		1745				

Rev. 1-3-13

Rev. - - DENOTES SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION, CONSTRUCTION DIVISION, CHICAGO, ILLINOIS
 PROJECT NO. 3098-R, CONTRACT NO. 60L79, SHEET NO. 11 OF 95

DESIGNED: RG	DRAWN: RG	CHECKED: MGR	DATE: MARCH, 2012	REVISED: -	REVISED: -	REVISED: -	REVISED: -
STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES			
F.A.U. RT# 1587	SECTION 3098-R	COUNTY COOK	TOTAL SHEETS 95	SHEET NO. 11	SCALE: SHEET NO. OF SHEETS STA. TO STA.		
				ILLINOIS FED. AID PROJECT CONTRACT NO. 60L79			