

1	2	3	4	5	6	7
LOCATION	EARTH EXCAVATION	UNSUITABLE OR UNSTABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOP SOIL FURNISH AND PLACE
	CU YD	CU YD	CU YD	CU YD	CU YD	SQ YD
McCarthy Road	1290	3365	1097	2705	-1609	6114
Walker Road	835	1470	710	395	315	3703
TOTAL	2125	4835	1806	3100	-1294	9817

EARTHWORK

I:\6710\671018 - McCarthy at Walker Intersection\_imp\CADD\CADD SHEETS\60L79-ht-schedule.dgn

FILE NAME =	USER NAME = rge11	DESIGNED - RG	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - RG	REVISED -					1587	3098-R	COOK	95	19
	PLOT SCALE = 100.0000' / in.	CHECKED - MGR	REVISED -		CONTRACT NO. 60L79							
	PLOT DATE = 10/19/2012	DATE - MARCH, 2012	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT				