

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	85% FED - 15% STATE 0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	36	36					
25200110	SODDING, SALT TOLERANT	SO YD	36	36					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	26	26	1				
40600300	AGGREGATE (PRIME COAT)	TON	130	130					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	49	49					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	310	310					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	35	35					
40603148	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, M80	TON	3677	3677					
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, M80	TON	3634	3634	1				
42001300	PROTECTIVE COAT	SO YD	42	42					
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SO YD	32439	32439					
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	150	150					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	110	110					


SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	85% FED - 15% STATE 0005					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	15	15					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	515	515					
56109210	WATER VALVES TO BE ADJUSTED	EACH	4	4					
63500310	REMOVE AND REINSTALL DELINEATORS	EACH	28	28					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD T01501	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD T01701	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2480	2480					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	76.6	76.6					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	27520	27520					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	160	160					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	410	410					

REV. 1-3-13

* SPECIALTY ITEMS
 NON-PARTICIPATING ITEMS

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES							CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
				0005										0005					
70500270	TEMPORARY PAVEMENT MARKING	FOOT	270	270						#88600600	DETECTOR LOOP REPLACEMENT	FOOT	764	764					
	- LINE 16"																		
70500280	TEMPORARY PAVEMENT MARKING	FOOT	580	580						X2020110	GRADING AND SHAPING SHOULDERS	UNIT	150	150					
	- LINE 24"									#4068500	PRELIMINARY TEST STAIR	EACH	2	2					
70501000	WORK ZONE PAVEMENT MARKING REMOVAL	50 FT	850	850						X6050310	FRAMES AND LIDS TO BE ADJUSTED	EACH	12	12					
											(SPECIAL)								
#78000100	THERMOPLASTIC PAVEMENT MARKING	50 FT	76.6	76.6						Z0004562	COMBINATION CONCRETE CURB AND GUTTER	FOOT	215	215					
	- LETTERS AND SYMBOLS										REMOVAL AND REPLACEMENT								
#78000200	THERMOPLASTIC PAVEMENT MARKING	FOOT	27520	27520						Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5					
	- LINE 4"																		
#78000400	THERMOPLASTIC PAVEMENT MARKING	FOOT	160	160						Z0050850	TEMPORARY INFORMATION SIGNING	50 FT	102.8	102.8					
	- LINE 6"																		
#78000600	THERMOPLASTIC PAVEMENT MARKING	FOOT	410	410						Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
	- LINE 12"																		
#78000610	THERMOPLASTIC PAVEMENT MARKING	FOOT	270	270															
	- LINE 16"																		
#78000650	THERMOPLASTIC PAVEMENT MARKING	FOOT	580	580															
	- LINE 24"																		
#78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	420	420															
78300200	RAISED REFLECTIVE PAVEMENT MARKER	EACH	380	380															
	REMOVAL																		

2



215 215

△

△ REV. 1-11-13

△ Rev. 1-3-13

* SPECIALTY ITEMS
 NON-PARTICIPATING ITEMS