SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		85% FEDERAL 15% STATE 0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	60	60					
25200110	SODDING, SALT TOLERANT	SQ YD	60	60					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	57	57					
40600300	AGGREGATE (PRIME COAT)	TON	285	285					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	107	107					
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	239	239					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2694	2694					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1216	1216					
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	580	580					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	71	71					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	6172	6172					
	* SPECIALTY ITEMS								

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		85% FEDERAL 15% STATE 0005					
42001300	PROTECTIVE COAT	SQ YD	198	198					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	234	234					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	54383	54383					
44000600	SIDEWALK REMOVAL	SQ FT	234	234					
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	915	915					
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	4538	4538					
44022029	PARTIAL DEPTH REMOVAL 3"	SQ YD	1213	1213					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	721	721					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	200	200					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	655	655					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	200	200					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	300	300					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	445	445					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	24	24					

FILE NAME = c:\pw_work\pw1dot\pughsd\d0246874\Illinois.sht.plan.dgn	USER NAME = pughsd	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 10/18/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TORRENCE AVE. (IL RTE. 83 (GLENWOOD DYER RD.) TO STEGER RD.)
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 1 OF 3 SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2937	2010-112-RS	COOK	32	3
		CONTRACT NO. 60M44		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT